



## State of Minnesota Department of Transportation

## Aggregates Test Report

Office of Materials and Road Research

1400 Gervais Avenue

Maplewood, MN 55109

Sample ID Number: CO-PS12-0035

Project Number: For Info Only

Field ID: 203  
Date Sampled:  
Date Received: 12/10/2012  
Approved: 12/18/2012 9:53  
TH Number:  
Depth: 4.00 to 8.00  
Grade Spec:  
Spec Class:  
Quality Spec:  
Plant Name:  
Comment: 43-23-36

Billing Agency:  
Project Engineer: D. MARTIN  
Submitter: C. JENNINGS  
IAS Name:  
Pit #:  
Pit Name:  
Pit Owner:  
Sampled From: WILLIAMS T COUNTY FOREST  
Usage: DNR PROSPECTING

Test Procedures: AASHTO T-19, T-21, T-27(M), T-30(M), T-84(M), T-85(M), T-96(M), T-104(M), T-113(M), T-176(M), T-248(M), T-304 Method A, ASTM C123, ASTM C535, ASTM D3042, ASTM D4791(M), Micro Deval(MP), Percent Crushing(MP) M = MN/DOT Modified MP = MN/DOT Procedures

% Passing Sieve:	Lab Test	Field Test	Spec. Limits	
			Low	High
50mm (2")	100			
37.5mm (1 1/2")	99			
31.5mm (1 1/4")	98			
25.0mm (1")	97			
19.0mm (3/4")	95			
12.5mm (1/2")	93			
9.5mm (3/8")	90			
4.75mm (#4)	83			
2.36mm (#8)	75			
2.00mm (#10)	72			
1.18mm (#16)	65			
600um (#30)	54			
425um (#40)	46			
300um (#50)	39			
150um (#100)	24			
75um (#200)	17.1			

% Shale in Sand	***0.0
% Spall Argillite	1.2
% Misc. Spall	1.48
% Carbonate	2.4
% NonSpall Argillite	1.7
% TotalSpallSpall	***0.0
% BA Spall +4	2.7

\* Value does not meet Spec  
~ Value out of Field Lab Tolerance  
\*\*\* Trace (0.00 - 0.05) Detected  
% Shale in Sand N.C. = Trace

☐ Meets Requirements  
☐ Does Not Meet Requirements  
☒ For Info Only  
☐ Incentive/Disincentive

☐ Unable to Verify  
☐ Unable to Verify, Not Enough Material Supplied  
☐ Within Lab-Field Tolerance  
☐ Out of Lab-Field Tolerance

Comments:  
AITKIN CO.

Copies To  
DNR - H. ARENDS

Charge: 1 - 1012  
1 - 1013  
1 - 1014  
1 - 1029

Report Approved By: