



- ① PARKING LOT IMPROVEMENTS
- ② VAULT TOILET
- ③ PAY BOX/ WAYFINDING
- ④ TRASH/RECYCLING
- ⑤ STONE WALL
- ⑥ INTERPRETIVE CENTER FOOTPRINT
- ⑦ INTERPRETIVE SIGN
- ⑧ EXISTING SMALL POND
- ⑨ SHELTER/EVENT (~36-60 PEOPLE)
- ⑩ FLOATING FLOOR
- ⑪ BIKE RACKS
- ⑫ SIOUX QUARTZITE BLUFF

- Pros**
- Adaptive reuse of Manfred house footprint and compatible design of new shelter
 - Accessible picnic shelter
 - Minimal impact on landscape

- Cons**
- Shelter over critical snake habitat; impact potentially minimized by floating floor
 - Majority of Interpretive Center structure removed/alterd to accommodate shelter and address structural deficiencies



C PERSPECTIVE C

In this concept, the trailhead improvements and the disposition of the Interpretive Center remain the same as shown in Concept 01. A new picnic shelter has been added to the Interpretive Center footprint in the location of a former sunken living room. The location takes advantage of the same vantage point as the living area and incorporates the triangular fireplace. A new floor for the shelter would be built over the existing building slab to cover the heaving slab and provide an accessible, uniform surface.

