

Appendix A, Big 39 and Little 39 Stream Restoration Site Plans

# BID SET - NOT FOR CONSTRUCTION BIG AND LITTLE 39 STREAM RESTORATION

NEAR SILVER BAY LAKE COUNTY, MN 10/15/2021











BID SET NOT FOR CONSTRUCTION

### **GENERAL CONSTRUCTION NOTES:**

- 1. THE WORK ON THIS PROJECT SHALL ADHERE TO THE FOLLOWING SPECIFICATIONS. STANDARDS AND/OR REGULATIONS: MN DOT STANDARD SPECIFICATIONS FOR CONSTRUCTION, 2018 EDITION, THE FOLLOWING SPECIFICATIONS EITHER MODIFY OR REPLACE APPROPRIATE MN DOT SPECIFICATIONS.
- 2. INSTREAM STRUCTURES SHALL BE INSTALLED AS THE CHANNEL IS BEING CONSTRUCTED AND NOT POST CONSTRUCTION
- 3. WHERE PRACTICABLE, EXISTING TREES AND VEGETATION SHOULD BE LEFT IN PLACE TO FACILITATE NATURAL REGENERATION AND SOIL STABILIZATION.
- 4. DEFINITIONS:
  - A. BANKFULL ELEVATION IS THE POINT OF INCIPIENT FLOODING IN AN ALLUVIAL CHANNEL. THIS ELEVATION IS THE REFERENCE FOR DEPTHS ON OR ALONG THE CHANNEL PROFILE AND STRUCTURES DESCRIBED IN THESE SHEETS.
  - B. THE BANKFULL BENCH IS A CONSTRUCTED FLOODPLAIN ADJACENT TO THE CHANNEL. THE BANKFULL BENCH IS CONSTRUCTED AT THE BANKFULL ELEVATION.
  - THE THALWEG IS THE LOWEST PORTION OF THE CHANNEL THE VANE LENGTH IS THE STRAIGHT LINE DISTANCE
  - BETWEEN THE VANE ARM AND A LINE TANGENT TO THE STREAMBANK AT THE POINT WHERE THE VANE ARM INTERSECTS THE STREAMBANK.
  - E. THE VANE ANGLE IS THE ANGLE BETWEEN THE VANE ARM AND A LINE TANGENT TO THE STREAMBANK AT THE POINT WHERE THE VANE ARM INTERSECTS THE STREAMBANK.
  - SOD MATS ARE GRASS AND WILLOW TRANSPLANTS THAT STILL CONTAIN ROOTING DEPTH. APPROXIMATELY 9-12IN OF DEPTH WILL BE NEEDED WHEN HARVESTING THE SOD MATS.
- 6. THE CONTRACTOR SHALL HAVE AT LEAST ONE GPS ASSISTED EXCAVATOR ON SITE FOR SETTING STRUCTURES AND GRADING THE ENGINEER WILL PROVIDE A TIN FILE FOR LOADING INTO GPS OPERATED EQUIPMENT. DEPENDING ON ENCOUNTERED CONDITIONS SOME SHIFTING OF THE STREAM CHANNEL MAY BE NECESSARY. ANY COST ASSOCIATED WITH CHANGING STRUCTURE LOCATIONS OR ALIGNMENT SHALL BE CONSIDERED INCIDENTAL TO CONSTRUCTION. STAKING MAY BE OMITTED FOR PORTIONS OF THE STREAM WHEN SURVEY-GRADE GPS IS USED TO CONSTRUCT THE CHANNEL. IF GPS IS USED IN LIEU OF STAKING THE CHANNEL IN THE FIELD, THE CONTRACTOR ASSUMES ALL RESPONSIBILITY FOR THE STREAM BEING CONSTRUCTED AS DESIGNED, INCLUDING ANY ISSUES RELATED TO PROJECTIONS, BASE POINTS OR CONVERSION OF DIGITAL TERRAIN MODELS.
- PRIOR TO CLEARING AND GRUBBING, CONTRACTOR SHALL MARK THE LIMITS OF CLEARING NEAR TREES FOR VERIFICATION OF INTENT BY THE ENGINEER. SOME MINOR ADJUSTMENT OF CHANNEL ALIGNMENT MAY BE REQUIRED TO PRESERVE TREES OR MINIMIZE IMPACT TO TREES
- CONTRACTOR SHALL MINIMIZE. TO THE MAXIMUM EXTENT POSSIBLE, IMPACTS TO THE ADJACENT TREES. CONSTRUCTION EQUIPMENT TRACKS AND PATHWAYS SHALL BE GRADED AND RECONTOURED AFTER CONSTRUCTION TO PREVENT RILL AND GULLY EROSION.
- THE PROPOSED GRADING IS SHOWN ON THESE PLAN SHEETS. THE CONTRACTOR MAY EXTEND THE LIMITS OF DISTURBANCE ONLY WITH THE APPROVAL OF THE ENGINEER.
- 10. CONTRACTOR SHALL USE AN EXCAVATOR WITH A HYDRAULIC THUMB TO INSTALL INSTREAM STRUCTURES.
- 11. CHANNEL RELOCATION WORK SHALL BE COMPLETED AND STABILIZED PRIOR TO ALLOWING FLOW TO ENTER INTO THE NEWLY CONSTRUCTED STREAM CHANNEL. THE CONTRACTOR SHALL NOT OPEN UP MORE THAN 200 FEET OF CHANNEL WITHOUT EROSION CONTROL BLANKET IN PLACE OR BY APPROVAL OF THE ENGINEER.
- 12. THE PROPOSED STREAM CHANNEL SHALL BE CONSTRUCTED BY FIRST GRADING THE FLOODPLAIN ADJACENT TO THE CHANNEL TO THE ELEVATION INDICATED ON THESE PLANS. THIS MAY BE DONE AS GENERAL EXCAVATION. THE PROPOSED STREAM CHANNEL SHALL THEN BE EXCAVATED TO THE PROPER DEPTHS INDICATED ON THE PROFILE AND PROPOSED CONTOURS. THIS SHALL BE DONE AS SPECIALIZED EXCAVATION AND IS TYPICALLY ACCOMPLISHED WITH A TRACK EXCAVATOR. THE PROFILES AND CONTOURS SHOWN PROVIDE WIDTHS AND SLOPES FOR AID IN CONSTRUCTING THE CHANNEL TO THE APPROPRIATE DIMENSIONS. THE THALWEG CAN FIRST BE EXCAVATED TO THE POINT INDICATED ON THE PROFILE. EXCAVATION AND FINE GRADING OF THE CROSS SECTIONS SHALL THEN BE PERFORMED AS SHOWN ON THE TYPICAL CROSS SECTIONS AND PROPOSED CONTOURS. ANY STOCKPILING OF MATERIALS OR "DOUBLE HANDLING" NECESSARY TO BUILD THE CHANNEL SHALL BE CONSIDERED INCIDENTAL TO CONSTRUCTION.
- 13. IF THE EXISTING GROUND IS LESS THAN 0.2 FEET HIGHER THAN

- THE PROPOSED BANKFULL ELEVATION, IT IS NOT NECESSARY TO EXCAVATE MATERIAL TO THE PROPOSED ELEVATION SHOWN ON THE PROFILE.
- 14. THE SURFACE OF ALL INSTREAM STRUCTURES SHALL BE FINISHED TO A SMOOTH LINE IN ACCORDANCE WITH THE LINES, GRADES. AND CROSS SECTIONS OR ELEVATIONS SHOWN ON THE DRAWINGS. THE DEGREE OF FINISH FOR THE VANE SLOPES AND INVERT ELEVATIONS SHALL BE WITHIN 0.1 VERTICAL FEET OF THE GRADES AND ELEVATIONS INDICATED. ALL GAPS OR VOIDS BETWEEN THE ROCKS SHALL BE PLUGGED WITH SMALL GRAVEL TO FORM A TIGHT-FITTING SEAL
- 15. CONSTRUCTION SPECIFICATIONS FOR BANKFULL CHANNEL DIMENSIONS OR CROSS SECTIONS WILL BE HELD TO THE DIMENSIONS SHOWN ON THE TYPICAL CROSS SECTIONS. **ELEVATIONS SHALL BE CONSTRUCTED WITHIN 0.1 VERTICAL** FEET; WIDTHS AND MEAN DEPTHS MUST FALL WITHIN THE RANGES SHOWN IN THE DRAWINGS.
- 16. THE IN-STRUCTURE BID ITEMS SHALL INCLUDE ALL LABOR AND MATERIALS NECESSARY TO CONSTRUCT THE STRUCTURE. BID ITEMS INCLUDE SEEDING, PLANTING, AND MULCH AND EROSION CONTROL BLANKETS AND INCLUDE ALL LABOR AND MATERIALS NECESSARY TO STABILIZE AREAS DISTURBED DURING CONSTRUCTION OF STRUCTURES. AFTER THE STRUCTURE IS COMPLETE AND FLOW IS RESTORED TO THE CHANNEL, SOME ADJUSTMENT TO THE STRUCTURE OR ADDITIONAL STABILIZATION MEASURES MAY BE NECESSARY TO ACHIEVE DESIRED EFFECT. ANY COSTS ASSOCIATED WITH THESE ADJUSTMENTS SHALL BE CONSIDERED INCIDENTAL TO CONSTRUCTION.
- 17. THE CONSTRUCTED STREAM CHANNEL SHALL BE STABILIZED AS SOON AS POSSIBLE. SEE EROSION CONTROL BLANKET DETAIL. THE BLANKET SHALL BE ROLLED OUT IN THE DIRECTION OF THE ANTICIPATED RUN-OFF FLOW. INSTALL BLANKET IN ACCORDANCE WITH DETAIL SHOWN HEREIN. REWORKING OF AREAS THAT DO NOT ESTABLISH VEGETATION OR BECOME UNSTABLE SHALL BE NECESSARY IF THE EROSION CONTROL BLANKET SEPARATES FROM THE SOIL. SEE SEEDING AND PLANTING DETAIL FOR BLANKET SPECIFICATIONS. SEEDING OF THE BANKFULL BENCH SHALL BE IN ACCORDANCE WITH THE PLANTING TABLE.
- 18. THE HARVESTING AND INSTALLATION OF LIVE STAKES SHALL BE PERFORMED ONLY DURING THE DORMANT SEASON TYPICALLY BETWEEN NOVEMBER 1 AND APRIL 15. CONTRACTOR SHALL NOTIFY ENGINEER 7 DAYS PRIOR TO HARVESTING TO REVIEW AND APPROVE ALL HARVESTING SITES. UPON APPROVAL BY ENGINEER, THE CONTRACTOR SHALL BE RESPONSIBLE FOR HARVESTING AND TRANSPORTING THE LIVE STAKE CUTTINGS TO THE JOB SITE.
- 19. LIVE STAKES SHALL BE INSTALLED ALONG THE OUTSIDE MEANDER BEND AND ALONG RIFFLES WHERE INDICATED ON THE DRAWINGS AND DETAILS. LIVE STAKES SHALL BE INSTALLED INTO THE EROSION CONTROL BLANKET IN ADDITION TO THE DEAD STAKES.
- 20. EXCESS SPOIL MATERIAL MAY BE SPREAD AND GRADED ONSITE OR IN THE ONSITE PIT AS APPROVED BY THE ENGINEER. PLACEMENT OF ANY ON-SITE OR OFF-SITE SPOIL MATERIAL SHALL BE CONSIDERED INCIDENTAL TO CONSTRUCTION.
- 21. CONTRACTOR SHALL CALL GOPHER STATE ONE CALL FOR UTILITY MARKING AT LEAST 48 HOURS PRIOR TO START OF CONSTRUCTION. THE LOCATIONS OF THE UTILITIES SHOWN ON THESE DRAWINGS ARE APPROXIMATE ONLY (UTILITY QUALITY LEVEL D) AND MAY NOT BE ACCURATE. LOCATING UTILITIES IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. THE ENGINEER AND PROJECT OWNER WILL NOT BE RESPONSIBLE FOR ANY DAMAGES TO UTILITIES.
- 22. AFTER CONSTRUCTION, THE ACCESS ROADS LEADING TO THE PROJECT SITE SHALL BE RESTORED TO AS GOOD OR BETTER CONDITION THAN BEFORE CONSTRUCTION AT THE ENGINEER'S DISCRETION.

# SURVEY NOTES:

THE ELEVATIONS SHOWN HEREIN ARE BASED ON DATA SURVEY THAT ENCOMPASSES THE EXISTING GROUND SURFACE FROM WHICH ALL COMPUTATIONS FOR CUT/FILL ARE BASED. SLIGHT DISCREPANCIES BETWEEN THE EXISTING GROUND DIGITAL SURFACE AND FIELD CONDITIONS CAN RESULT IN SIGNIFICANT VARIATIONS IN TOTAL EXCAVATED QUANTITIES. THUS, THE CONTRACTOR SHALL COMPARE QUANTITIES OF MATERIAL EXCAVATED TO THOSE SHOWN ON THE DRAWINGS TO MANAGE THE MOVEMENT OF MATERIAL ACROSS THE SITE.

## TOPOGRAPHIC INFORMATION:

EXISTING GROUND SURFACES ARE BASED ON A SURVEY COMPLETED IN 2020 BLENDED WITH STATE OF MN LIDAR. BENCHMARKS WERE SET THROUGHOUT THE SITE AND CAN BE PROVIDED AT ANY TIME. CHANGES IN EXISTING SURFACES SHALL BE INCIDENTAL TO CONSTRUCTION.

### **SPECIAL GRADING NOTE:**

THE AGREED UPON INTENT OF THIS GRADING PLAN IS TO MAINTAIN A "LIVE" SURFACE SO THAT ANY CHANGES THAT ARISE DURING CONSTRUCTION CAN BE QUICKLY ENCOMPASSED INTO THE THREE-DIMENSIONAL SURFACE GENERATED DURING THIS DESIGN PROCESS. AS SUCH, FINE TUNING OF THE SURFACE THAT WOULD ELIMINATE THE APPEARANCE OF JAGGED CONTOUR LINES WHERE SLIGHT VARIATIONS BETWEEN THE EXISTING AND PROPOSED SURFACES WAS NOT COMPLETED.

### MN DOT SPECIAL PROVISIONS

THE FOLLOWING SPECIAL PROVISIONS REFER TO THE SPECIFIC SPEC SECTIONS REFERENCED IN THE BID TABULATIONS

### MN DOT SPECIAL PROVISIONS

THE FOLLOWING ARE MODIFICATIONS TO THE MN DOT STANDARD **SPECIFICATION** 

### 2571 PLANT INSTALLATION AND ESTABLISHMENT

### 2571.3 K PLANT ESTABLISHMENT PERIOD

REPLACE ALL SECTIONS WITH THE FOLLOWING: THE CONTRACTOR SHALL REPLACE ALL TREES AFTER ONE YEAR OF PLANTING TO AN INITIAL STOCKING RATE OF 75 PERCENT. THE PLANTING WILL BE CONSIDERED SUCCESSFUL IF AFTER ONE YEAR 75 PERCENT OF THE TREES ARE ALIVE. REPLACEMENT OF THE NUMBERS TO REACH THAT CRITERIA IS THE RESPONSIBILITY OF THE CONTRACTOR.

### MEASUREMENT AND PAYMENT

2571.601 PAYMENT WILL BE MADE ON THE BASIS OF EACH TREE OR SHRUB INSTALLED AS PER DETAILED IN PLANS.

### **2577 SOIL BIOENGINEERED SYSTEMS**

# **TOEWOOD**

ITEM INCLUDES INSTALLATION OF ALL TOE WOOD AND ASSOCIATED COIR WRAP AND MATERIALS AS INDICATED ON THE TOE WOOD DETAIL

# MEASUREMENT AND PAYMENT

2571.603 PAYMENT WILL BE MADE ON THE BASIS OF LINEAR FEET OF TOEWOOD INCLUSIVE FURNISHING FROM STAGING AREA AND INSTALLING ALL MATERIALS AS SHOWN ON THE PLANS. CLIFFS WILL PROVIDE ALL THE WOOD MATERIAL STAGED IN THE AREA SHOWN ON THE PLANS.

# **LOG J HOOK**

ITEM INCLUDES INSTALLATION OF ALL LOG J HOOKS ASSOCIATED GRADING AND MATERIALS AS INDICATED ON THE LOG J-HOOK DETAIL

# MEASUREMENT AND PAYMENT

2571.601 PAYMENT WILL BE MADE ON THE BASIS OF EACH J-HOOK INSTALLED. FURNISHING FROM STAGING AREA AND INSTALLING ALL MATERIALS AS SHOWN ON THE PLANS. CLIFFS WILL PROVIDE ALL THE WOOD AND BOULDER MATERIAL STAGED IN THE AREA SHOWN ON THE PLANS.

# **LOG VANE**

ITEM INCLUDES INSTALLATION OF ALL LOG VANES ASSOCIATED GRADING AND MATERIALS AS INDICATED ON THE LOG VANE DETAIL

# MEASUREMENT AND PAYMENT

2571.602 PAYMENT WILL BE MADE ON THE BASIS OF EACH J-HOOK INSTALLED. FURNISHING FROM STAGING AREA AND INSTALLING ALL MATERIALS AS SHOWN ON THE PLANS. CLIFFS WILL PROVIDE ALL THE WOOD MATERIAL STAGED IN THE AREA SHOWN ON THE PLANS.

# **SOIL LIFTS**

ITEM INCLUDES INSTALLATION OF SOIL LIFTS AND ASSOCIATED GRADING AND MATERIALS AS INDICATED ON THE SOIL LIFT AND ALDER TRANSPLANT DETAIL.

# MEASUREMENT AND PAYMENT

2571.604 PAYMENT WILL BE MADE ON THE BASIS OF LINEAR FEET OF SOIL LIFT INSTALLED. THIS ITEM INCLUDES FURNISHING AND INSTALLING ALL MATERIALS AS SHOWN ON THE DETAIL

### **ALDER TRANPLANTS**

ITEM INCLUDES INSTALLATION OF ALDER TRANSPLANTS AND ASSOCIATED GRADING AND MATERIALS AS INDICATED ON THE SOIL LIFT AND ALDER TRANSPLANT DETAIL. THE ALDER SHALL BE SELECTED FROM ON SITE SOURCES. CONTRACTOR SHALL SELECT AND REMOVE ALL ALDER IN A MANNER THAT ALLOWS FOR PLACEMENT ON THE NEWLY CONSTRUCTED STREAM BANKS WHERE NOTED ON THE PLANS.

### MEASUREMENT AND PAYMENT

2571.605 PAYMENT WILL BE MADE ON THE BASIS OF LINEAR FEET OF ALDER TRANSPLANT INSTALLED. THIS ITEM INCLUDES FURNISHING AND INSTALLING ALL MATERIALS AS SHOWN ON THE DETAIL.

### **BOULDER CONSTRUCTED RIFFLE**

ITEM INCLUDES INSTALLATION OF ALL BOULDER CONSTRUCTED RIFFLE ASSOCIATED GRADING AND MATERIALS AS INDICATED ON THE BOULDER CONSTRUCTED RIFFLE DETAIL

### MEASUREMENT AND PAYMENT

2571.606 PAYMENT WILL BE MADE ON THE BASIS OF EACH BOULDER CONSTRUCTED RIFFLE INSTALLED. FURNISHING FROM STAGING AREA AND INSTALLING ALL MATERIALS AS SHOWN ON THE PLANS. CLIFFS WILL PROVIDE ALL THE BOULDER MATERIAL STAGED IN THE AREA SHOWN ON THE PLANS. CONTRACTOR TO SUPPLY RIP RAP MATERIAL.

### **GRAVEL RIFFLE**

ITEM INCLUDES INSTALLATION OF ALL GRAVEL RIFFLES AND ASSOCIATED GRADING AND MATERIALS AS INDICATED ON THE GRAVEL RIFFLE DETAIL.

### MEASUREMENT AND PAYMENT

2571.607 PAYMENT WILL BE MADE ON THE BASIS OF EACH GRAVEL RIFFLE INSTALLED. FURNISHING FROM STAGING AREA AND INSTALLING ALL MATERIALS AS SHOWN ON THE PLANS. CLIFFS WILL PROVIDE ALL THE WOOD AND BOULDER MATERIAL STAGED IN THE AREA SHOWN ON THE PLANS. CONTRACTOR TO SUPPLY ALL RIP RAP MATERIAL.

### **ROCK GLIDE RIFFLE**


ITEM INCLUDES INSTALLATION OF ALL ROCK GLIDE RIFFLES ASSOCIATED GRADING AND MATERIALS AS INDICATED ON THE LOG J-HOOK DETAIL

# MEASUREMENT AND PAYMENT

2571.608 PAYMENT WILL BE MADE ON THE BASIS OF EACH ROCK GLIDE RIFFLE INSTALLED. FURNISHING FROM STAGING AREA AND INSTALLING ALL MATERIALS AS SHOWN ON THE PLANS. CLIFFS WILL PROVIDE ALL THE WOOD AND BOULDER MATERIAL STAGED IN THE AREA SHOWN ON THE PLANS. CONTRACTOR TO SUPPLY ALL RIP RAP MATERIAL.

: GET	APPRV	\$	KA KA	KA KA	₹ ¥	X	×	X	X
DRAWN BY: GET									
CHECKED BY: MJG	DESCRIPTION	DRAFT 30% DESIGN	DRAFT 60%	DRAFT 90%	BID SET	××	×	XX	××
APPROVED BY: KA									
APPRO	REV	_	2	3	4	XX	×	XX	×

39 TI S  $\mathbf{\Omega}$ RESIL SILVER E COUNTY  $\circ$ 0 BIG, REA NEA LAKE





**BID SET** NOT FOR CONSTRUCTION


DATE: 10/15/2021


SHEET NUMBER


OF 50
















































































BASE WIDTH



STREAM LAYOUT TYPICALS

NOT TO SCALE

STREAM NAME		BIG 39				
STREAM TYPE		B4c				
DRAINAGE AREA, DA (SQ MI)		23				
DESIGN PARAMETERS	MINIMUM	MEDIAN	MAXIMUM			
MEAN RIFFLE DEPTH, $D_{BKF}$ (FT)		1.8				
RIFFLE WIDTH, W <sub>BKF</sub> (FT)		33.0				
WIDTH-TO-DEPTH RATIO, [W <sub>BKF</sub> /D <sub>BKF</sub> ]		18.0				
RIFFLE CROSS-SECTION AREA, A <sub>BKF</sub> (SQ FT)		60.0				
MAX RIFFLE DEPTH, D <sub>MAX</sub> (FT)		2.9				
POOL WIDTH, W <sub>BKFP</sub> (FT)		36.0				
POOL CROSS-SECTION AREA, A <sub>BKFP</sub> (SQ FT)		80.0				
MAX POOL DEPTH, D <sub>MAXP</sub> (FT)		6.0				
RIFFLE LENGTH, L <sub>RIF</sub> (FT)	1.4	3.0	4.3			
POOL LENGTH, L <sub>P</sub> (FT)	1.5	1.9	2.8			
ENTRENCHMENT RATIO, ER [W <sub>FPA</sub> /W <sub>BKF</sub> ]		2.2				
BELT WIDTH, W <sub>BLT</sub> (FT)		80.0				
RADIUS OF CURVATURE, RC (FT)	3.0	4.4	9.0			
POOL-TO-POOL SPACING, P-P (FT)	3.5		7.0			
VALLEY SLOPE, VS (FT/FT)		0.0019				
WATER SURFACE SLOPE, WS (FT/FT)		0.0020				
SINUOSITY, K = SL/VL (FT/FT)		1.0300				

APPROVED BY: KA	CHECKED BY: MJG	DRAWN BY: GET	GET
	DESCRIPTION		APPRV
	DRAFT 30% DESIGN		\$
	DRAFT 60%		\$
	DRAFT 90%		Ą
	BID SET		Α <del>Υ</del>
	X		×
	X		×
	XX		XX
	×		×

SIREAM RESIDRATION
NEAR SILVER BAY
LAKE COUNTY, MN
BID SET - NOT FOR CONSTRUCTIO

NORTHSHORE MINING CO
10 OUTER DR
SILVER BAY, MN 55614

BEAVER
RIVER
CONSULTING

BEAVER RIVER CONSULTING, LLC.
5752 EAGLE VIEW DRIVE
DULUTH, MN 55803


BID SET NOT FOR CONSTRUCTION

DATE: 10/15/2021

NOT TO SCALE


SHEET NUMBER

36 OF 50





BASE WIDTH




POINT OF

CURVATURE (PC)

STREAM LAYOUT TYPICALS

STREAM NAME		LITTLE 3	9	
STREAM TYPE		B4c		
DRAINAGE AREA, DA (SQ MI)		2		
DESIGN PARAMETERS	MINIMUM	MEDIAN	MAXIMUM	
MEAN RIFFLE DEPTH, D <sub>BKF</sub> (FT)		1.1		
RIFFLE WIDTH, W <sub>BKF</sub> (FT)		18		
WIDTH-TO-DEPTH RATIO, [W <sub>BKF</sub> /D <sub>BKF</sub> ]		16		
RIFFLE CROSS-SECTION AREA, A <sub>BKF</sub> (SQ FT)		20		
MAX RIFFLE DEPTH, D <sub>MAX</sub> (FT)		1.8		
POOL WIDTH, W <sub>BKFP</sub> (FT)		20		
POOL CROSS-SECTION AREA, A <sub>BKFP</sub> (SQ FT)		27		
MAX POOL DEPTH, D <sub>MAXP</sub> (FT)		3.6		
RIFFLE LENGTH, L <sub>RIF</sub> (FT)	1.7 3 4.7			
POOL LENGTH, L <sub>P</sub> (FT)	1.3 2.4 3.4			
ENTRENCHMENT RATIO, ER [W <sub>FPA</sub> /W <sub>BKF</sub> ]		2		
BELT WIDTH, W <sub>BLT</sub> (FT)		45		
RADIUS OF CURVATURE, RC (FT)				
POOL-TO-POOL SPACING, P-P (FT)	3.5	5.5	7.7	
VALLEY SLOPE, VS (FT/FT)	0.12-093			
WATER SURFACE SLOPE, WS (FT/FT)		varies		
SINUOSITY, K = SL/VL (FT/FT)		1.02		



SIREAM RESIORATION
NEAR SILVER BAY
LAKE COUNTY, MN
BID SET - NOT FOR CONSTRUCTION

NORTHSHORE MINING CO
10 OUTER DR
SILVER BAY, MN 55614




BID SET NOT FOR CONSTRUCTION

DATE: 10/15/2021

NOT TO SCALE


SHEET NUMBER

37 OF 50



GRAVEL RIFFLE PLAN VIEW

NOT TO SCALE




NOT TO SCALE

# NOTES:

- THE GRAVEL AND COBBLE SUBSTRATE USED FOR THIS FEATURE SHOULD BE PREFERENTIALLY HARVESTED FROM THE ARMOR LAYER OF THE EXISTING CHANNEL AND AMENDED OR SORTED AS NOTED BY THE REGION OF THE RIFFLE/GLIDE.
- 2. SORTING AND SIEVING OF THE HARVESTED RIFFLE SUBSTRATE IS INCIDENTAL TO THE CONSTRUCTION OF THIS STRUCTURE
- . SELECT RIFFLE MATERIAL SHALL HAVE A GRADATION OF 25 % BY VOLUME OF CLASS III RIP RAP, 25 PERCENT BY VOLUME CLASS II RIP RAP, AND 50 PERCENT BY VOLUME HARVESTED IN PLACE STREAM BED MATERIAL.
- 4. SELECT RIFFLE MATERIAL WILL BE PLACED AT A MINIMUM THICKNESS OF 1.5'.
- 5. THE SELECT RIFFLE MATERIAL WILL BE PLACED SUCH THAT, IN CROSS-SECTION, ITS LOWEST ELEVATION OCCURS IN THE CENTER OF THE CHANNEL AS PER THE DETAIL.
- 6. HABITAT BOULDERS SHALL BE PLACED IN THE RIFFLE SUCH THAT NOT MORE THAN  $1/3-\frac{1}{2}$  THE DIAMETER OF THE BOULDER PROTRUDES ABOVE THE STREAM BED. AS SHOWN SOME OF THE BOULDERS SHALL BE PLACED IN GROUPINGS OF 3 IN ORDER TO CREATE DOWNSTREAM SCOUR, THE BOULDERS SHALL BE 18-36" IN DIAMETER.
- 7. SELECT RIFFLE MATERIAL SHALL BE COMPACTED USING TRACK EQUIPMENT SUCH THAT FUTURE SETTLEMENT OF THE MATERIAL IS KEPT TO A MINIMUM.
- 8. RE-DRESSING OF CHANNEL AND BANKFULL BENCH/FLOODPLAIN WILL LIKELY BE REQUIRED FOLLOWING INSTALLATION OF IN-STREAM STRUCTURES AND SHALL BE CONSIDERED INCIDENTAL TO CONSTRUCTION.

APPRO	APPROVED BY: KA	CHECKED BY: MJG	DRAWN BY: GET	GET
REV		DESCRIPTION		APPRV
_		DRAFT 30% DESIGN		\$
2		DRAFT 60%		\$
ဗ		DRAFT 90%		\$
4		BID SET		\$
×		×		×
×		×		×
XX		××		XX
×		×		×

SIREAM RESIORATION
NEAR SILVER BAY
LAKE COUNTY, MN
BID SET - NOT FOR CONSTRUCTIO




BID SET NOT FOR CONSTRUCTION


DATE: 10/15/2021

NOT TO SCALE

SHEET NUMBER


38 OF 50






PLAN-SYMBOL

SECTION A-A'





### NOTE:

THE DEPARTURE ANGLE SHOWN ABOVE IS DEPICTED IN SUCH A WAY TO EMPHASIZE DETAIL. ACTUAL DEPARTURE ANGLE AND STRUCTURE LOCATION SHALL BE AS SHOWN ON THE PLAN AND PROFILE SHEETS AND WILL BE PROVIDED TO THE CONTRACTOR AS A 2004 FORMAT DWG FILE AND LN3 FILE.


### NOTES:

- LOGS SHALL HAVE MINIMUM DIAMETER OF 14" AND MINIMUM LENGTH OF 25 FEET.
- 2. ALL LOGS SHALL BE RELATIVELY STRAIGHT AND LIMBS SHALL BE TRIMMED FLUSH.
- 3. FOOTER LOGS/BOULDERS ARE LOGS/BOULDERS PLACED TO PROVIDE A FOUNDATION AND SCOUR PROTECTION FOR THE HEADER LOGS/BOULDERS.
- 4. HEADER LOGS/BOULDERS SHALL BE UNDERLAIN BY FOOTER LOGS/BOULDERS UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
- 5. HEADER LOGS ARE THE TOP MOST LOGS USED IN EACH LOG STRUCTURE. ALL HEADER LOGS CAN BE SEEN PROTRUDING FROM THE WATER SURFACE DURING EXTREMELY LOW FLOWS.
- 6. HEADER LOGS SHALL BE OFFSET SLIGHTLY DOWNSTREAM OF THE FOOTING LOGS WHERE SCOUR POOLS ARE ANTICIPATED TO FORM AS SHOWN IN THE DETAIL.
- 7. SILL LOGS SHALL BE PLACED PERPENDICULAR TO THE BANKFULL FLOW DIRECTION.
- 8. THE FOOTER LOGS SHALL EXTEND FROM THE SILL LOG TO THE END OF THE HEADER LOG TOWARD THE BANK.
- 9. HOOK BOULDERS SHALL EXTEND FROM THE HEADER LOG TO BEYOND BANKFULL WIDTH.
- 10. SET INVERTS AT ELEVATION SHOWN ON THE PLAN AND PROFILE SHEETS. INVERTS AND ELEVATIONS WILL BE PROVIDED TO THE CONTRACTOR AS A 2004 FORMAT DWG FILE AND LN3 FILE. NO ELEVATIONS OF THE LOG DROPS STRUCTURE MAY VARY FROM THE PLAN LOCATIONS WITHOUT DIRECTIONS FROM ENGINEER.
- 11. HEADER LOG SHALL TIE INTO THE STREAM BANK AT A MAXIMUM ELEVATION OF 1/4 DMAX (MEASURED AT THE NEXT DOWNSTREAM RIFFLE) BELOW BANKFULL ELEVATION AND A MINIMUM ELEVATION OF 1/2 DMAX (MEASURED AT THE NEXT DOWNSTREAM RIFFLE) BELOW BANKFULL ELEVATION UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
- 12. CUTTING OF THE SILL LOG ROOTWAD MAY BE REQUIRED TO PREVENT THE ROOTWAD FROM PROTRUDING ABOVE THE BANKFULL ELEVATION.

- 13. ALL GAPS/VOIDS LARGER THAN 1 INCH
  BETWEEN THE HEADER AND FOOTING LOGS
  SHALL BE CHINKED WITH LIMBS AND/OR BRUSH
  ON THE UPSTREAM SIDE PRIOR TO PLACEMENT
  OF THE 700 GRAM COIR WITH CAT 3N 2S
  BACKER BLANKET.
- 14. ALL GAPS/VOIDS LARGER THAN 1 INCH BETWEEN THE HEADER AND FOOTING BOULDERS SHALL BE CHINKED WITH GRAVEL AND COBBLES.
- 15. ON THE STREAMBANK SIDE OF THE LOG AND/OR BOULDERS BACKER BLANKET SHALL BE PLACED AS SHOWN FOR THE ENTIRE LENGTH OF THE LOG.
- 16. SELECT BACKFILL AND SOIL BACKFILL MATERIAL SHALL BE COMPACTED SUCH THAT FUTURE SETTLEMENT OF THE MATERIAL IS KEPT TO A MINIMUM.
- 17. NAIL BACKER BLANKET TO EDGE OF HEADER LOG AND BACKFILL AS SHOWN IN THE PLANVIEW DETAIL.
- 18. THE SURFACE OF THIS STRUCTURE SHALL BE FINISHED TO A SMOOTH AND COMPACT SURFACE IN ACCORDANCE WITH THE LINES, GRADES, AND CROSS—SECTIONS OR ELEVATIONS SHOWN ON THE DRAWINGS. THE DEGREE OF FINISH FOR INVERT ELEVATIONS SHALL BE WITHIN 0.1 FT OF THE GRADES AND ELEVATIONS INDICATED.
- 19. RE-DRESSING OF CHANNEL AND BANKFULL BENCH/FLOODPLAIN WILL LIKELY BE REQUIRED FOLLOWING INSTALLATION OF IN-STREAM STRUCTURES AND SHALL BE CONSIDERED INCIDENTAL TO CONSTRUCTION.
- 20. SEE THE PLANTING DETAIL FOR HIGH DENSITY LIVE STAKING.
- 21. NO LIVE STAKES SHALL BE INSTALLED ON THE UPSTREAM SIDE OF THE LOG VANE AT OR BELOW THE TIE—IN ELEVATION OF THE HEADER LOG WITH THE STREAM BANK UNLESS OTHERWISE DIRECTED BY THE ENGINEER.

G F G	APPRV	\$	KA	₹	ΑΆ	XX	×	×	×
DKAWN BY:									
CHECKED BY: MJG DKAWN BY: GET	DESCRIPTION	DRAFT 30% DESIGN	DRAFT 60%	DRAFT 90%	BID SET	XX	X	X	×
PPROVED BY: KA									
7777	REV	_	2	3	4	X	×	×	×

BIG AND LITTLE 39
STREAM RESTORATION
NEAR SILVER BAY
LAKE COUNTY, MN
BID SET - NOT FOR CONSTRUCTION



BID SET NOT FOR CONSTRUCTION


DATE: 10/15/2021


NOT TO SCALE

OF


50

SHEET NUMBER





STREAM RESTORATION
NEAR SILVER BAY
LAKE COUNTY, MN
BID SET - NOT FOR CONSTRUCTION




BID SET NOT FOR CONSTRUCTION

DATE: 10/15/2021


NOT TO SCALE

SHEET NUMBER
41 OF 50



700 G COIR EROSION CONTROL FABRIC WITH CAT 3N 2S BACKER BLANKET

OR ALDER TRANSPLANTS AS NOTED



# NOTES SOIL LIFTS:

- 1. THE SOIL BACKFILL USED FOR LIFTS AND TOPSOIL USED FOR LAYERING WITH THE LIVE BRANCHES SHALL BE FREE OF ANY LARGE ROOTS OR WOODY DEBRIS AND SHALL GENERALLY BE FREE FROM ANY GRAVEL OR COBBLE MATERIAL.
- 2. SOIL BACKFILL SHALL BE COMPACTED SUCH THAT FUTURE SETTLING WILL BE KEPT TO A MINIMUM: YET. NOT SUCH THAT THE UNDERLYING SOIL LIFT IS DISPLACED OR DAMAGED.
- 3. THE TOP OF THE BACKFILL FOR THE FIRST LIFT SHALL BE SLOPED AT APPROXIMATELY 2% AWAY FROM THE STREAM.
- 4. PLACE SOIL BACKFILL UP TO THE LIFT HEIGHT SPECIFIED OF NO GREATER THAN 1.0 FT BEING CAREFUL NOT TO PUSH/PULL OR TEAR THE FABRIC PREVIOUSLY PLACED.
- 5. THE EROSION CONTROL BLANKET SHALL BE PULLED AS TIGHT AS POSSIBLE WITHOUT TEARING OR EXCESSIVELY DISTORTING THE FABRIC. THE COIR BLANKET USED FOR THE SOIL LIFT SHALL BE 13' WIDE AND PLACED AS SHOWN IN THE DETAIL
- 6. SECURE THE EROSION CONTROL AND NON-WOVEN MATTING IN PLACE BY STAKING THE END OF THE EROSION CONTROL FABRIC WITH WOODEN STAKES ON 1.5-FOOT CENTERS.
- 7. THE SURFACE OF THIS STRUCTURE SHALL BE FINISHED TO A SMOOTH AND COMPACT SURFACE IN ACCORDANCE WITH THE LINES, GRADES, AND CROSS-SECTIONS OR ELEVATIONS SHOWN ON THE DRAWINGS. THE DEGREE OF FINISH FOR ELEVATIONS SHALL BE WITHIN 0.1 FT OF THE GRADES AND ELEVATIONS INDICATED OR APPROVED BY THE ENGINEER.
- 8. RE-DRESSING OF CHANNEL AND BANKFULL BENCH/FLOODPLAIN WILL LIKELY BE REQUIRED FOLLOWING INSTALLATION OF IN-STREAM STRUCTURES AND SHALL BE CONSIDERED INCIDENTAL TO CONSTRUCTION.

# NOTES ON ALDER TRANSPLANTS:

- 1. ALL ALDER SHALL BE OBTAINED FROM ON SITE SOURCES
- 2. CUT ALDER TO 2 FEET ABOVE ROOT BALL
- 3. EXCAVATE TRANSPLANTS FROM SOURCE AND STORE FOR NO MORE THAN 48 HOURS BEFORE PLACEMENT ON SITE
- 4. REMOVE A MINIMUM OF 1 FOOT OF ROOT MATERIAL BELOW THE SURFACE OF THE ALDER
- 5. PLACE ON THE BANK AS SHOWN CONTINUOUSLY ALONG THE BANKS AS NOTED IN THE PLAN SHEETS
- 6. PLACE ALDER TRANSPLANTS A MINIMUM OF 3 FEET BACK FROM THE STREAM BANKFULL EDGE

GET	APPRV	₹	₹	×	×	×	×	XX	×
DRAWN BY: GET									
CHECKED BY: MJG	DESCRIPTION	DRAFT 30% DESIGN	DRAFT 60%	DRAFT 90%	×	×	XX	XX	×
APPROVED BY: KA									
APPRO	REV	_	2	က	×	×	×	×	×




**BID SET** NOT FOR CONSTRUCTION

DATE: 4/19/2021

NOT TO SCALE

SHEET NUMBER

42 OF 50



DETAIL - BOULDER CONSTRUCTED RIFFLE

NOT TO SCALE

**BOULDER** 

MIN. 4'

PLAN VIEW



# **BOULDER CONSTRUCTED RIFFLE CONSTRUCTED MARCH 2019**

# NOTES:

- 1. BOULDERS FOR THE CONSTRUCTED RIFFLE MUST BE A MIN. OF 1-2 TON BOULDER WITH A MIN. DIAMETER OF 2-3'.
- 2. THE UPSTREAM AND DOWNSTREAM HEADER BOULDERS SHALL BE UNDERLAIN BY FOOTER BOULDERS UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
- 3. HEADER BOULDERS ARE THE TOP MOST BOULDERS USED IN EACH STRUCTURE. HEADER BOULDERS FOR THIS STRUCTURE ARE ONLY VISIBLE BETWEEN THE INNER BERMS.
- HEADER BOULDERS SHALL BE OFFSET SLIGHTLY UPSTREAM OF THE FOOTER BOULDERS. FOOTER BOULDERS SHALL BE INSTALLED BEFORE THE HEADER BOULDERS.
- SET INVERTS AT ELEVATION SHOWN ON PLAN AND PROFILE SHEETS. INVERTS AND ELEVATIONS WILL BE PROVIDED TO THE CONTRACTOR AS A 2014 FORMAT DWG FILE. NO ELEVATIONS OF THE CONSTRUCTED RIFFLE ARMS MAY VARY FROM THE PLAN LOCATIONS WITHOUT DIRECTION FROM THE ENGINEER.
- 6. THE DROP IN ELEVATION ACROSS THE STRUCTURE SHALL NOT EXCEED 0.5FT UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
- 7. MINI-VANES WILL BE SPACED IN THE RIFFLE AS A FUNCTION OF THE RIFFLE LENGTH.
- 8. THE MOST UPSTREAM RIFFLE MINI-VANE ARM SHALL BE PLACED SUCH THAT THE BANK TIE-IN IS ON THE SAME SIDE AS THE NEXT UPSTREAM OUTSIDE BEND IN ORDER TO SERVE AS A VANE AND HELP DIRECT STREAM FLOW AWAY FROM THE PREVIOUS OUTSIDE BEND. LOCATION OF ALL RIFFLE VANE ARMS ARE SHOWN ON THE PLAN AND PROFILE SHEETS.
- 9. THE MOST DOWNSTREAM MINI-VANE ARM SHALL BE PLACED SUCH THAT THE HIGH POINT IS ON THE SAME SIDE AS THE NEXT DOWNSTREAM OUTSIDE BEND IN ORDER TO HELP DIRECT STREAM FLOW FROM THE NEXT OUTSIDE BEND.
- 10. THE VERTICAL SLOPE OF EACH MINI-VANE ARM SHALL NOT EXCEED 10% UNLESS OTHERWISE DIRECTED BY THE ENGINEER. THE SLOPES WILL BE DICTATED BY THE WIDTH-TO-DEPTH RATIO OF THE REACH, TYPICAL RIFFLE INNER BERM CHANNEL, VERTICAL DROP OVER THE LOG, AND LOG DIAMETER.

- 11. ALL GAPS/VOIDS LARGER THAN 2" BETWEEN THE HEADER AND FOOTER BOULDERS SHALL BE HAND CHINKED WITH COBBLE AND GRAVEL ON THE UPSTREAM SIDE. ALL CHINKING SHALL BE APPROVED BY THE ENGINEER BEFORE THE MINI-VANES ARE BACKFILLED.
- 12. BACKFILL VANES WITH SELECT BACKFILL MATERIAL AS SHOWN AND DEFINED IN THE CONSTRUCTED RIFFLE DETAIL. BACKFILL MATERIAL TO HAVE A GRADATION OF 25% BY VOLUME OF CLASS II RIP RAP, 25 PERCENT BY VOLUME CLASS I RIP RAP, AND 50 PERCENT BY **VOLUME HARVESTED IN PLACE STREAM BED** MATERIAL.
- 13. SELECT BACKFILL AND SOIL BACKFILL MATERIAL SHALL BE COMPACTED SUCH THAT FUTURE SETTLEMENT OF THE MATERIAL IS KEPT TO A MINIMUM.
- 14. THE SURFACE OF THIS STRUCTURE SHALL BE FINISHED TO A SMOOTH AND COMPACT SURFACE IN ACCORDANCE WITH THE LINES, GRADES, AND CROSS-SECTIONS OR ELEVATIONS SHOWN ON THE DRAWINGS. THE DEGREE OF FINISH FOR INVERT ELEVATIONS SHALL BE WITHIN 0.1' OF THE GRADES AND ELEVATIONS INDICATED, PROVIDED ANY HEIGHT DOES NOT EXCEED MAX. ALLOWABLE DROP OF 0.5' FOR THIS STRUCTURE.
- 15. RE-DRESSING OF CHANNEL AND BANKFULL BENCH/FLOODPLAIN WILL LIKELY BE REQUIRED FOLLOWING INSTALLATION OF IN-STREAM STRUCTURES AND SHALL BE CONSIDERED INCIDENTAL TO CONSTRUCTION.
- 16. FOOTER DEPTH ON ALL STRUCTURES REQUIRING FOOTERS SHALL BE 6 TIMES GREATER THAN THE DROP BETWEEN THE STRUCTURE AND THE FOOTERED STRUCTURE DIRECTLY UPSTREAM.
- 17. THE DEPARTURE ANGLE SHOWN ABOVE IS DEPICTED IN SUCH A WAY TO EMPHASIZE DETAIL. ACTUAL DEPARTURE ANGLE SHALL BE AS SHOWN ON THE PLAN AND PROFILE SHEETS WILL BE PROVIDED TO THE CONTRACTOR AS A 2014 FORMAT DWG FILE AND LN3 FILE.

APPROVED BY: KA         CHECKED BY: MJG           REV         DESCRIPTION           2         DRAFT 30% DESIGN           3         DRAFT 60%           4         BID SET           XX         XX           XX         XX           XX         XX           XX         XX           XX         XX           XX         XX	A PAPRV A KA K
×	×

BIG RE/ NE/





**BID SET** NOT FOR CONSTRUCTION


DATE: 10/15/2021

NOT TO SCALE

SHEET NUMBER 50 OF







### SEED MIX ZONE 0 AND 1

GRASS SEED	15 LBS./ACRE				
Big bluestem (Andropogon gerardii)	20%				
Fringed brome (Bromus ciliatus) Blue-joint grass (Calamagrostis canadensis) Caterpillar Sedge (Carex crinita) Poverty oats (Danthonia spicata) Slender Wheatgrass (Elymus trachycalum) Virginia wild rye (Elymus virginicus) American manna (Glyceria grandis) Fowl bluegrass (Poa palustris) Cord grass (Spartina pectinata)	8% 2% 5% 10% 12% 13% 10% 5%				

Wildflower Seed	32oz./acre
Yarrow (Achillea millefolium) Fragrant giant hyssop (Agastache foeniculum Swamp milkweed (Asclepias incarnata) Common milkweed (Asclepias syriaca) Fireweed (Epilobium angustifolium)	2% 10% 10% 10% 2%
Boneset (Eupatorium perfoliatum) Joe-Pye weed (Eutrochium maculatum) Common ox-eye (Heliopsis helianthoides) Wild bergamot (Monarda fistulosa) Black-eyed Susan (Rudbeckia hirta)	8% 5% 5% 10% 5%
Stiff goldenrod ( <i>Solidago rigida</i> ) Blue vervain ( <i>Verbena hastata</i> ) Golden alexanders ( <i>Zizia aurea</i> )	7% 20% 6%

# ZONE 2 AND 3 SEED MIX, PLUS

Grasses 15 lbs/ac Forbs 32 oz/ac

Grasses	Mix <sup>9</sup>
Big bluestem (Andropogon gerardii)	10%
Fringed brome (Bromus ciliatus)	8%
Poverty oats ( <i>Danthonia spicata</i> )	30%
Canada wild rye ( <i>Elymus canadensis</i> )	18%
Slender Wheatgrass (Elymus trachycalum)	24%
Little Bluestem (Schizachrium scoparium)	10%

, , ,	
Forbs	Mix %
Yarrow (Achillea millefolium)	1%
Fragrant giant hyssop (Agastache foeniculum)	12%
Canada anemone (Anemone canadensis )	2%
Common milkweed (Asclepias syriaca)	10%
Fireweed (Epilobium angustifolium)	3%
Large-leaved aster (Eurybia macrophylla)	1%
Grass-leaved goldenrod (Euthamia graminifolia)	2%
Stiff sunflower (Helianthus pauciflorus)	5%
Common ox-eye (Heliopsis helianthoides)	12%
Wild bergamot (Monarda fistulosa)	5%
Meadow rose ( <i>Rosa blanda</i> )	3%
Black-eyed Susan ( <i>Rudbeckia hirta</i> )	8%
Gray goldenrod ( <i>Solidago nemoralis</i> )	4%
Upland goldenrod (Solidago ptarmicoides)	5%
Stiff goldenrod ( <i>Solidago rigida</i> )	5%
Lindleys aster (Symphyotrichum ciliolatum)	9%
Blue vervain ( <i>Verbena hastata</i> )	5%
Golden alexanders ( <i>Zizia aurea</i> )	8%

# ZONE 0

# PLANTING AREA-

6.5' WIDE NEAR CREEK AREA MINUS TOE WOOD CANOPY-

THE FOLLOWING CANOPY PLANTS SHALL BE 1.5' HEIGHT CONTAINERIZED STOCK. PLANT AT 8 FOOT SPACING ABOVE BANKFULL ELEVATION:

- WHITE SPRUCE (PICEA GLAUCA)-90%
- \*WHITE CEDAR (THUJA OCCIDENTALIS)-10%

## SUB-CANOPY-

THE FOLLOWING SUB-CANOPY PLANTS SHALL BE 1.5' HEIGHT CONTAINERIZED STOCK. PLANT THE FOLLOWING EVERY 10 FOOT SPACING, AT OR ABOVE BANKFULL ELEVATION.

- 1. SPECKLED ALDER (ALNUS INCANA)-50%
- 2. RED-OSIER DOGWOOD (CORNUS SERICEA)-50%

## TRANSPLANTS:


TRANSPLANT WILLOW AND DOGWOOD SHRUBS FROM THE EXCAVATED AREA AS NOTED ON PLAN SHEETS

## SEED AND COIR AND BACKER BLANKET

• BLANKET MAIN CHANNEL WITH 6.5' WIDE 700 GRAM COIR BLANKET AND BACKED WITH MN DOT CATEGORY 3N, 2S, EROSION CONTROL BLANKET. INSTALL 2' LONG, 2"X2" WOOD STAKES WITH A ROOFING NAIL AT THE TOP TO SECURE THE BLANKET, INSTALL STAKES EVERY 5' ALONG BLANKET EDGES AND EVERY 5' DOWN THE CENTERLINE OF THE BLANKET. SEED WITH MIX NOTED ON THIS DETAIL SHEET WITH 25 LBS/ACRE OF COVER CROP AS APPROVED BY ENGINEER.

# **ACCESS TRAILS**

orbs	Mix %
arrow (A <i>chillea millefolium</i> )	1%
ragrant giant hyssop (Agastache foeniculum)	12%
anada anemone (Anemone canadensis )	2%
ommon milkweed (Asclepias syriaca)	10%
ireweed (Epilobium angustifolium)	3%
arge-leaved aster ( <i>Eurybia macrophylla</i> )	1%
irass-leaved goldenrod (Euthamia graminifolia)	2%
tiff sunflower (Helianthus pauciflorus)	5%
ommon ox-eye ( <i>Heliapsis helianthoides</i> )	12%
Vild bergamot ( <i>Monarda fistulosa</i> )	5%
Neadow rose ( <i>Rosa blanda</i> )	3%
lack-eyed Susan ( <i>Rudbeckia hirta</i> )	8%
iray goldenrod ( <i>Solidago nemoralis</i> )	4%
lpland goldenrod (Solidago ptarmicoides)	5%
tiff goldenrod ( <i>Solidago rigida</i> )	5%
indleys aster (Symphyotrichum ciliolatum)	9%
lue vervain ( <i>Verbena hastata</i> )	5%
iolden alexanders (Zizio gureg.)	8%



ZONE PLANTING TYPICAL CROSS SECTION DETAIL

# ZONE 1

# SEEDING AND PLANTING AREA-

FLOODPLAIN AREA NOTED ON PLAN SHEET

### CANOPY

THE FOLLOWING CANOPY PLANTS SHALL BE 1.5' HEIGHT CONTAINERIZED STOCK. PLANT AT 8 FOOT SPACING:

- WHITE SPRUCE (PICEA GLAUCA) -50%
- YELLOW BIRCH (BETULA ALLEGHANIENSIS)-10%
- 3. \*WHITE PINE (PINUS STROBUS) -40%

## **SUB-CANOPY**

THE FOLLOWING SUB-CANOPY PLANTS SHALL BE 1.5' HEIGHT CONTAINERIZED STOCK. PLANT THE FOLLOWING AT 10 FOOT SPACING,

- 1. CHOKE CHERRY (PRUNIS VIRGINIANA)-20%
- 2. NANNYBERRY (VIBURNUM LENTAGO)-20%
- 3. JUNEBERRIES (AMELANCHIER SPP.)-30%
- 4. BUSH HONEYSUCKLE (DIERVILLA LONICERA)-30%

# SEED AND APPLY EROSION CONTROL BLANKET

- APPLY TYPE CAT 3N2S EROSION CONTROL BLANKET, APPLY STAPLES AND BLANKET AS PER DETAIL ON SHEET??
- SEED WITH MIX NOTED ON THIS DETAIL SHEET WITH 25 LBS/ACRE OF COVER CROP.
- SCARIFY SOIL PRIOR TO SEEDING

## TREE PROTECTION:

\* SPECIES THAT REQUIRE 6' HIGH X 3.0' DIAMETER FENCING WITH 2 T-POSTS PLACED ON THE UPSTREAM SIDE OF THE TREE CAGE

### ACCESS ROADS AND TRAILS THIS AREA APPLIES TO GRASSED TRAILS NEAR STREAMS NOT EXISTING GRAVEL ROADS

## SEED, MULCH, SOIL

- APPLY WEED FREE STRAW MULCH
- SEEDAT 60LBS PER ACRE WITH MIX NOTED ON THIS DETAIL SHEET
- WITH 25 LBS/ACRE OF COVER CROP AS APPROVED BY ENGINEER.
- SCARIFY SOIL PRIOR TO SEEDING

# ZONE 2

### SEEDING AND PLANTING AREA-

SLOPE AREA FROM NEW FLOODPLAIN TO EXISTING GROUND

# **CANOPY**

THE FOLLOWING CANOPY PLANTS SHALL BE 1.5' HEIGHT CONTAINERIZED STOCK. PLANT AT 8 FOOT SPACING:

- 1. WHITE SPRUCE (PICEA GLAUCA) -30%
- 2. RED PINE (*PINUS RESINOSA*)-40%
- JACK PINE (PINUS BANKSIANA)- 20%
- 4. \*WHITE PINE (PINUS STROBUS) -10%

## **SUB-CANOPY**

THE FOLLOWING SUB-CANOPY PLANTS SHALL BE 1.5' HEIGHT CONTAINERIZED STOCK. PLANT THE FOLLOWING AT 10 FOOT SPACING,

- CHOKE CHERRY (PRUNIS VIRGINIANA)-20%
- 2. NANNYBERRY (VIBURNUM LENTAGO)-20%
- 3. JUNEBERRIES (AMELANCHIER SPP.)-20%
- 4. BUSH HONEYSUCKLE (DIERVILLA LONICERA)-20%

## SEED AND BLANKET

- APPLY CATEGORY 3N, 2S EROSION CONTROL BLANKET
- SEED AT 60LBS PER ACRE WITH MIX NOTED ON THIS DETAIL SHEET WITH 25 LBS/ACRE OF COVER CROP AS APPROVED BY ENGINEER.
- SCARIFY SOIL PRIOR TO SEEDING

# ZONE 3

SEEDING AND PLANTING AREA-

HIGH GROUND AREAS WHERE REED CANARY GRASS IS PRESENT ON **BIG 39 PROJECT** 

## TREES AND SHRUBS

• TREE AND SHRUB SPECIES AND DENSITY SHALL BE THE SAME AS ZONE 3.

# SEED, MULCH, SOIL

- APPLY WEED FREE STRAW MULCH
- REMOVE TOP 10" OF SOIL WITH REED CANARY GRASS PRESENT AND DISPOSE OF AT SITE APPROVED BY ENGINEER.
- SEEDAT 60LBS PER ACRE WITH MIX NOTED ON THIS DETAIL SHEET WITH 25 LBS/ACRE OF COVER CROP AS APPROVED BY ENGINEER.
- SCARIFY SOIL PRIOR TO SEEDING



CLIFFS NORTHSHORE MINING CO

10 OUTER DR



DULUTH, MN 55803

**BID SET** NOT FOR


CONSTRUCTION


DATE: 10/15/2021

NOT TO SCALE


SHEET NUMBER


OF 50






BLANKET STAPLE PATTERN






DITCH BLANKET STAPLE DETAIL




DITCH BLANKET CRITICAL POINTS (7)


# NOTES:

- 1) USE CHECK SLOT DETAIL (NO ALTERNATES).
- 2) PLACE DOUBLE ROW OF STAPLES STAGGERED 4" APART AND 4" ON CENTER.
- USE 6" X 6" TRENCH TO PLACE BLANKET. PLACE SINGLE ROW OF STAPLES ON TOP AND TRENCH SIDES AT 12" SPACING. BACKFILL TRENCH WITH SOIL AND TAMP.
- (4) PLACE SINGLE ROW OF STAPLES AT 12" SPACING.
- USE STAPLE CHECK FOR CHANNEL SLOPES LESS THAN 2.5%.
  GRADE AT 100' INTERVALS. PLACE DOUBLE ROW OF STAPLES
  STAGGERED 4" APART AND AT 4" SPACING.
- USE BLANKET CHECKS FOR THE FOLLOWING SLOPES: 2.5%-3% 100' INTERVALS 3%-5% 50' INTERVALS 5%-7% 25' INTERVALS
- CRITICAL POINTS SHALL BE SECURED WITH PROPER STAPLE PATTERNS.





CHECK SLOT ALTERNATIVE
PLACE SINGLE ROW STAPLES AT 12" SPACING
CHECK SLOT DETAILS



GENERAL BLANKET INSTALLATION REQUIREMENTS
REPP = ROLLED EROSION PREVENTION PRODUCT.


PREPARE SOIL AS PER SPECIFICATION 2574.

LAY PARALLEL OR PERPENDICULAR TO THE DIRECTION OF WATER FLOW.

OVERLAP ADJACENT STRIP EDGES A MINIMUM OF 4".

OVERLAP BLANKET 6" (MINIMUM) AT EACH END. OVERLAP BOTTOM END OF UPPER BLANKET OVER TOP END OF LOWER BLANKET. STAPLE ALONG OVERLAP EVERY 1.5".

THE UPPERMOST BLANKET OF ALL SLOPE APPLICATIONS MUST START IN A CHECK SLOT. IF SLOPE LENGTH (L) IS 100' OR GREATER, INSERT BLANKET INTO A CHECK SLOT ½ FROM THE BOTTOM OF THE SLOPE.



NEAR SILVER BAY
LAKE COUNTY, MN

T - NOT FOR CONSTRUCTION

CLIFFS

NORTHSHORE MINING CO
10 OUTER DR
SILVER BAY, MN 55614
---BEAVER
RIVER

BEAVER RIVER CONSULTING, LLC. 5752 EAGLE VIEW DRIVE

**DULUTH, MN 55803** 

CONSULTING


BID


BID SET NOT FOR CONSTRUCTION

DATE: 10/15/2021

NOT TO SCALE

SHEET NUMBER
48 OF 50







**BID SET** NOT FOR CONSTRUCTION

DATE:

NOT TO SCALE

10/15/2021

SHEET NUMBER

49 OF 50

	BIG/LITTLE 39 CREEKS STORMWATER POLLUTION PREVENTION PLAN (SWPPP)
	SWPPP PREPARATION DATE: 10/14/2021
	SWPPP CONTACT KEITH ANDERSON, BEAVER RIVER CONSULTING 5752 EAGLE VIEW DRIVE DULUTH,MN 55803 218-626-7450
	NATIONAL POLLUTION DISCHARGE ELIMINATION SYSTEM PERMIT NUMBER:
	CHAIN OF RESPONSIBILITY:
	BY SIGNING BELOW, ALL PARTIES AGREE TO FOLLOWING THE SWPPP SETFORTH.
	OWNER:PHONE#:
00 10, 2021 10:0 1:20 / 11	OPERATOR: PHONE#: SWPPP DESIGNER: KEITH ANDERSON, KEITH@BEAVERRIVERCONSULTING.COM PHONE#: CELL 218-626-7450  SWPPP INSPECTOR/MANAGER: PHONE#:  CONSTRUCTION SWPPP DESIGNATE: PHONE#: ESTIMATED PROJECT DATES: PROJECT START DATE: PROJECT END DATE: WATER BODY: BIG AND LITTLE 39 CREEKS, LAKE COUNTY MN
y, Octob	DNR WORK RESTRICTIONS: JULY 1-SEPTEMBER 15TH WITHOUT AMENDMENT
L LO I LD MOIN	MN DNR SPECIAL WATERS, ENSURE ANY EQUIPMENT WORKING IN THE WATER HAS BI WASHED AND IS FREE OF EXOTIC SPECIES
0.000	

CONTRACTOR SHOP DRAWING OF BMPS LOCATIONS AND TIMING: TO BE ATTACHED AT

DIVERSION PLANS: TO BE ATTACHED AT PRECONSTRUCTION MEETING

STAGING PLANS: TO BE ATTACHED AT PRECONSTRUCTION MEETING

DEWATERING PLANS: TO BE ATTACHED AT PRECONSTRUCTION MEETING

ASSOCIATED DOCUMENTS:

PROJECT PLANS

NPDES PERMIT

PROJECT DETAILS

SWPPP AMENDMENTS

**INSPECTION REPORTS** 

CERTIFICATION OF TRAINING(S)

PRECONSTRUCTION MEETING

PUBLIC WATERS WORK PERMIT

STORMWATER POLLUTION PREVENTION PLAN FOR THE **BIG/LITTLE 39 STREAM RESTORATION PROJECTS** 

PROJECT INFORMATION:

THE PROJECT INVOLVES THE RESTORATION OF TWO REACHES OF STREAM IN THE BIG AND LITTLE 39 WATERSHED AREA. FLOODPLAIN EXCAVATION AND CHANNEL REALIGNMENT WILL BE PERFORMED TO ALLOW THE STREAMS TO BE IMPROVED TO A NATURAL CONDITION.

PROJECT DESCRIPTION:

THIS PROJECT INVOLVES RESTORING HABITAT AND FLOODPLAINS TO PREVIOUSLY DITCHED CHANNELS USING FLUVIAL GEOMORPHOLOGY TECHNIQUES THAT WILL ADD FLOODPLAIN PROCESSES AND REESTABLISH RIFFLE AND POOL MORPHOLOGY THUS ENHANCING FISH HABITAT. THE RESTORATION WILL INCLUDE TOEWOOD BANK STABILIZATION AND COARSE RIFFLE STRUCTURES TO CONTROL THE DESIGN STREAM GRADE. EACH REACH WILL BE COMPLETED ON A PHASING SCHEDULE THAT WILL BE DEVELOPED AT THE PRE-CONSTRUCTION MEETING AND ALONG WITH CORRESPONDING SWPPP AMENDMENTS.

THE TOTAL DISTURBED ARE FOR THE PROJECT IS 12.5 ACRES.

THE TOTAL AREA OF IMPERVIOUS SURFACE PRE PROJECT 0 ACRES THE TOTAL AREA OF IMPERVIOUS SURFACE POST PROJECT, 0 ACRES

SEE INDEX FOR PLANS, DETAILS, SPECIFICATIONS, PHASING PLAN

REGULATORY CONTEXT:

SPECIAL OR IMPAIRED WATERS: THIS PROJECT DOES DISCHARGE TO SPECIAL WATERS, BIG AND LITTLE 39 CREEK. IN ADDITION TO THE MAIN STEM OF THE BEAVER RIVER WHICH IS AN MPCA IMPAIRED WATER.

THIS PROJECTS STORM WATER DISCHARGE IS NOT ANTICIPATED TO IMPACT ANY OF THE FOLLOWING: OUTSTANDING RESOURCE VALUE WATERS, CALCAREOUS FENS, PROPERTIES LISTED BY THE NATIONAL REGISTER OF HISTORIC PLACES OR ARCHAEOLOGICAL SITES AND IS NOT SUBJECT TO ADDITIONAL REGULATIONS DUE TO ANY FORMAL ENVIRONMENTAL REVIEW. ENDANGERED OR THREATENED SPECIES. WETLANDS DELINEATED AND IMPACT IS COORDINATED WITH ARMY CORPS OF ENGINEERS ALONG WITH THE WETLAND CONSERVATION ACT PANEL.

DEPARTMENT OF NATURAL RESOURCES HAS AUTHORITY OF WORK BELOW ORDINARY HIGH WATER LEVEL. PUBLIC WATERS WORK PERMIT SHALL BE OBTAINED AND ADHERED TO.

STORMWATER POLLUTION PREVENTION PLAN (SWPPP) IMPLEMENTATION RESPONSIBILITIES:

- 1. THE OWNER AND CONTRACTOR ARE IDENTIFIED BY THE BID DOCUMENTS.
- 2. CONTRACTOR SHALL VERIFY THAT ALL PERMITS HAVE BEEN OBTAINED.
- CONTRACTOR SHALL PERFORM SITE INSPECTIONS, RECORD KEEPING AND RECORD RETENTION IN ACCORDANCE WITH ALL PERMITS.
- 4. CONTRACTOR SHALL INSTALL ALL SEDIMENT CONTROL BEST-MANAGEMENT-PRACTICES (BMP) AND CONSTRUCTION ENTRANCES PRIOR TO SITE GRADING, EXCAVATION, STOCKPILING OR DISTURBING EXISTING **VEGETATIVE COVER**
- 5. CONTRACTOR SHALL PERFORM SITE GRADING, EXCAVATION, STOCKPILING WORK IN ACCORDANCE WITH SWPPP. 6. CONTRACTOR SHALL INSTALL, INSPECT, MONITOR AND MAINTAIN TEMPORARY AND PERMANENT EROSION SEEN CONTROL BMP AS SHOWN ON PLANS, CONTINUOUSLY DURING DURATION OF WORK.
  - 7. CONTRACTOR SHALL INITIATE SOIL STABILIZATION IMMEDIATELY AND STABILIZE ALL EXPOSED SOILS WITHIN 7 DAYS AFTER CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY
  - 8. CONTRACTOR SHALL REPLACE OR REPAIR EROSION CONTROL AND SEDIMENT CONTROL BMPS IMMEDIATELY IF IT
  - IS FOUND THAT THEY ARE NOT FUNCTIONING PROPERLY. 9. CONTRACTOR SHALL PERFORM SITE RESTORATION ACTIVITIES FOR PERMANENT VEGETATION ESTABLISHMENT.
  - 10. CERTIFIED SWPPP INPECTOR/MANAGER IDENTIFIED AT THE PRECONSTRUCTION MEETING SHALL INSPECT THE ENTIRE PROJECT AT LEAST ONCE EVERY SEVEN (7) DAYS DURING ACTIVE CONSTRUCTION AND WITHIN 24 HOURS AFTER A RAINFALL EVENT GREATER THAN 0.5 INCHES IN 24 HOURS.
  - 11. INSPECTIONS SHALL BE CONDUCTED WITH THE PROVIDED SWPPP INSPECTION WORKSHEET
  - 12. REDUNDANT BMP SHALL BE INSTALLED IF FREQUENT FAILURE OR EXCESSIVE MAINTENANCE IS NOTED AND SWPPP WILL BE AMENDED TO THAT EFFECT
  - 13. CONTRACTOR SHALL REMOVE SEDIMENT CONTROL DEVICES AT COMPLETION OF PROJECT AND SUBMIT A NOTICE OF TERMINATION TO MINNESOTA POLLUTION CONTROL AGENCY.
  - 14. CONTRACTOR SHALL ENSURE THAT THE PUBLIC WATERS PERMIT STIPULATIONS ARE FOLLOWED.

RECORD RETENTION

- 1. SWPPP RECORDS SHOULD BE MAINTAINED BY OWNER FOR THREE YEARS AFTER FINAL STABILIZATION. 2. CHANGES MADE TO SWPPP PLAN IMPLEMENTATION SHALL BE RECORDED AS SWPPP AMENDMENTS WITH 24
- 3. SWPPP AMENDMENTS SHALL BE ACCOMPANIED BY NOTIFICATION OF CHANGES TO SWPPP INSPECTOR/MANAGER. 3. A COPY OF SWPPP PLAN SHALL BE MAINTAINED ON SITE OR IN CONSTRUCTION VEHICLE DURING ACTIVE
- 4. INSPECTIONS WILL BE RECORDED WITH 24 HOURS IN WRITING AND RETAINED WITH SWPPP RECORD IN A DESIGNATED LOCATION.

CONSTRUCTION ACTIVITY FIELD REQUIREMENTS:

- A. ALL FIELD REQUIREMENTS SHALL BE PERFORMED IN ACCORDANCE WITH THE REQUIREMENTS OF THE SWPPP. 1. THE CONTRACTOR MUST IMPLEMENT SWPPP AND PROVIDE BMPS IDENTIFIED IN THE SWPPP IN A APPROPRIATE AND FUNCTIONAL MANNER.
- 2. THE CONTRACTOR SHALL RESPOND TO CHANGING SITE CONDITIONS AND IMPLEMENT/SUPPLEMENT EROSION PREVENTION AND SEDIMENT CONTROL MEASURES UTILIZED TO PROVIDE ADEQUATE PROTECTION OF DISTURBED SOILS AND ADEQUATE PREVENTION OF SEDIMENT TRANSPORT OFF-SITE. AT A MINIMUM, THE FOLLOWING STORM WATER POLLUTION PREVENTION CONSTRUCTION FIELD REQUIREMENTS SHALL BE FURNISHED BY THE CONTRACTOR.

B. EROSION PREVENTION PRACTICES

- 1. THE CONTRACTOR SHALL ATTEMPT TO PHASE ALL WORK TO MINIMIZE EROSION AND MAINTAIN VEGETATION COVER TO THE EXTENT POSSIBLE.
- 2. ALL EXPOSED SOILS WITH PERIMETER CONTROL BMPS MUST BE STABILIZED NO LATER THAN 7 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED, INCLUDING STOCKPILES WITH SIGNIFICANT SILT, CLAY OR ORGANIC COMPONENTS.
- 3. TEMPORARY OR PERMANENT ENERGY DISSIPATION AT PIPE OUTLETS MUST BE PROVIDED WITHIN 24 HOURS OF CONNECTING TO A SURFACE WATER.
- 5. TOPSOIL WILL BE SALVAGED AND STOCKPILED FOR REAPPLICATION SO AS TO ENSURE MAXIMUM GROWTH POTENTIAL.

C. SEDIMENT CONTROL PRACTICES

CONTRACTOR SHALL BE RESPONSIBLE FOR THE FOLLOWING SEDIMENT CONTROL PRACTICES DUE TO THE LOCATION AND UNIQUE NATURE OF THE PROJECT WORKING IN THE STREAMS, DOWNGRADIENT SEDIMENT CONTROL IS NOT FEASIBLE, ALL EFFORTS WILL BE MADE TO CONTROL SEDIMENT BY PHASING THE STREAM PROJECT AS NOTED IN THE PLANS AND STABILIZING AND DIVERTING THE WATER DURING CONSTRUCTION. 2. TIMING AND INSTALLATION OF SEDIMENT CONTROL DEVICES CAN BE ADJUSTED BY CONTRACTOR TO ACCOMMODATE SHORT-TERM ACTIVITIES SUCH AS CLEARING AND GRUBBING OR VEHICLE PASSAGE. ANY SHORT TERM ACTIVITY MUST BE COMPLETED AS QUICKLY AS POSSIBLE AND THE SEDIMENT CONTROL PRACTICES MUST BE INSTALLED IMMEDIATELY AFTER THE ACTIVITY IS COMPLETED AND IN ALL CASES PRIOR TO THE NEXT PRECIPITATION

3. TEMPORARY SOIL STOCKPILES MUST HAVE SILT FENCE/TOP SOIL BERMS OR OTHER EFFECTIVE SEDIMENT CONTROL. SOIL STOCKPILES SHALL NOT BE PLACED WITH IN SURFACE WATERS OR STORMWATER CONVEYANCES. ALL STOCKPILES THAT WILL NOT BE DISTURBED FOR ONE MONTH OR LONGER SHALL BE PROTECTED FROM EROSION BY CONTRACTOR USING A COVER OF MULCH, EROSION CONTROL MATS OR PLASTIC SHEETING.

4. CONTRACTOR SHALL IMPLEMENT MEASURES TO CONTROL VEHICLE TRACKING OFFSITE IF NECESSARY.

D. DEWATERING AND BASIN DRAINING (IF APPLICABLE)

1. CONTRACTOR'S DEWATERING ACTIVITIES THAT HAVE SEDIMENT-LADEN DISCHARGE MUST DISCHARGE INTO A TEMPORARY OR PERMANENT SEDIMENTATION BASIN OR THROUGH SOME FORM OF BMP, SUCH AS A FILTER BAG, BY CONTRACTOR TO LIMIT SEDIMENT FROM LEAVING THE SITE TO ENSURE EFFLUENT WATER IS FREE OF SEDIMENT.

- I. DEWATERING PLANS SHALL BE FURNISHED TO SWPPP PERSONNEL AT TIME OF CONSTRUCTION. II. DEWATERING DISCHARGE POINTS MUST BE DISPERSED OVER PLYWOOD. NATURAL RIPRAP. SANDBAGS, PLASTIC SHEETING, OR OTHER ACCEPTED ENERGY DISSIPATING MEASURES IN A NON-EROSIVE MANNER.
- III. DEWATERING BMPS SHALL BE INSPECTED BY THE CONTRACTOR PERIODICALLY DAILY AND IMMEDIATELY MAINTAINED OR REPAIRED IF SEDIMENT-LADEN WATER IS BEING DISCHARGED.

E. SWPPP PERSONNEL SHALL BE RESPONSIBLE FOR PERFORMING THE FOLLOWING INSPECTIONS AND MAINTENANCE

- 1. ALL NONFUNCTIONAL BMPS SHALL BE REPAIRED, REPLACED WITHIN 24 HOURS AFTER DISCOVERY. CONTRACTOR SHALL PLACE ANY ADDITIONAL EROSION CONTROL MEASURES DEEMED NECESSARY BY THE ENGINEER WITH 24
- 2. THE SWPPP INSPECTOR MUST ROUTINELY INSPECT THE SITE ONCE EVERY 7 DAYS DURING ACTIVE CONSTRUCTION AND WITH 24 HOURS AFTER A RAINFALL EVENT GREATER THAN 0.5 INCHES IN 24 HOURS. 3. ALL SILT MUST BE REMOVED FROM SILT FENCE BY CONTRACTOR WHEN IT REACHES A HEIGHT EQUAL TO ONE-THIRD OF THE HEIGHT OF THE SILT FENCE. CONTRACTOR SHALL REPAIR SILT FENCE THAT IS NONFUNCTIONAL WITH 24 HOURS OF DISCOVERY
- 4. INSPECTIONS CAN BE SUSPENDED DUE TO FROZEN GROUND CONDITIONS UNTIL FIRST RUNOFF OCCURS OR CONSTRUCTION ACTIVITIES RESUME.

F. POLLUTION PREVENTION MEASURES

CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLEMENTING THE FOLLOWING POLLUTION MANAGEMENT MEASURES ON THE SITE:

- 1. SOLID WASTE: COLLECTED SEDIMENT, ASPHALT, CONCRETE MILLINGS, FLOATING DEBRIS, PAPER, PLASTIC, FABRIC, CONSTRUCTION AND DEMOLITION DEBRIS AND OTHER WASTES MUST BE DISPOSED OF PROPERLY AND MUST COMPLY WITH MPCA DISPOSAL REQUIREMENTS.
- 2. HAZARDOUS MATERIAL: HAZARDOUS SUBSTANCES MUST BE STORED IN APPROPRIATE CONTAINERS AND STEPS IMPLEMENTED TO PREVENT SPILLS, LEAKS, AND VANDALISM
- 3. ADEQUATE SUPPLIES TO CLEAN UP SPILLS MUST BE AVAILABLE ON SITE.
- 4. NO VEHICLE DEGREASING ON SITE.


G. DIVERSION

1. CONTRACTORS MUST PROVIDE DETAILS ON STREAM DIVERSION AT THE PRECONSTRUCTION MEETING. THIS INCLUDES BUT NOT LIMITED TO: PIPE SIZES, PUMP SIZES, DIVERSION CHANNEL SIZE, DIVERSION CHANNEL LOCATIONS, WITH ASSOCIATED DEWATERING PLANS IF APPLICABLE.

2. DIVERSION CAN BE ACHIEVED USING BERMS, ABANDONED CHANNELS, JERSEY BARRIERS, PIPES, SANDBAG DAMS, PLYWOOD DAMS, OR OTHER METHODS THAT ARE DEEMED APPROPRIATE FOR THE SITE.

FINAL STABILIZATION

- 1. ALL DISTURBED AREAS SHALL BE STABILIZED BY USING COIR MAT, EROSION CONTROL BLANKETS, MULCH, OR HYDROSEEDED AS PER VEGETATIVE DETAILS SHEETS
- 2. ALL DISTURBED AREAS SHALL BE PERMANENTLY STABILIZED BY SEED, SHRUBS, AND TREES AS SPECIFIED IN
- 3. TEMPORARY SEDIMENT EROSION CONTROL BMPS SHALL BE REMOVED AT PROJECT CLOSEOUT.



8 F S  $\mathbf{\Omega}$ REST SILVE COUNT  $\circ$ 0 四尺乙 



**BID SET** NOT FOR CONSTRUCTION

DATE: 10/15/2021

NOT TO SCALE

SHEET NUMBER 50 OF

# Appendix B, NHIS Review and Concurrence

### Memorandum

**To:** MNDNR Environmental Policy & Review Unit **From:** Tyler Conley, Mark Jacobson – Barr Engineering

Subject: Big and Little Thirtynine Creek Restoration Threatened and Endangered Species Review

Date: December 1, 2021

**Project:** 23381049

**c:** Nate Schroeder – Northshore Mining Company

Northshore Mining Company (Northshore) is in the process of permitting two stream mitigation projects related to the West Ridge Railroad and Tailings Basin Progression Project. The stream mitigation projects include the Big Thirtynine Creek and Little Thirtynine Creek Sites. The stream restoration locations are shown on **Figure 1**. This technical memorandum summarizes the results of the desktop review for the presence of endangered, threatened, and special concern (ETSC) species within the creek restoration extent **Figure 2**. The purpose of this memorandum is to identify the potential for ETSC species to be impacted by the proposed projects. On behalf of Northshore, Barr requests that the MDNR consider the documentation and conclusions of this review and provide a written determination addressing the sufficiency of this memo to fulfill the endangered and threatened species component of the Wetland Conservation Act (Minnesota Rule 8420.0515, subparts 1 and 2).

### 1.1 MNDNR NHIS Database Query

In November 2021, Barr queried the current NHIS database to identify any ETSC species that have been previously recorded within one mile of the stream restoration project extents. The database review indicated that no ETSC species have been previously identified within the restoration area. However, two state-listed special concern species have been identified within one mile of the project extents (**Table 1**).

Table 1 Rare Species Documented within One Mile of Big Thirtynine Creek and Little Thirtynine Creek Site According to MNDNR NHIS

Scientific Name	Common Name	Federal Status	State Status	Suitable Habitat Present?	Further Action Required?
Cladium mariscoides	Twig rush	None	Special Concern	Yes	No
Eleocharis nitida	Neat spikerush	None	Special Concern	Yes	No

### 1.1.1 Twig Rush (Cladium mariscoides)

Twig rush occurs mostly in fens, particularly prairie rich fens, northern rich fens, and calcareous fens (MDNR, 2021a). Twig rush is found in two locations within one mile of the project extents. Both

To: MNDNR EWR Environmental Policy & Review Unit From: Tyler Conley, Mark Jacobson – Barr Engineering

Subject: Big and Little Thirtynine Creek Restoration Threatened and Endangered Species Review

Date: December 1, 2021

Page: 2

populations are found within former borrow sites where clay soils had been excavated for basin construction. One location has approximately 50 stems in a single patch covering about 12 square meters. The other nearby location has around 500 stems in a single patch covering about 15 square meters (Barr, 2016). No fen plant communities are located within the project extents. Suitable habitat for twig rush may be present within the creek restoration area. However, the species is listed as special concern and is not legally protected under state endangered species law. No further action is required.

### 1.1.2 Neat Spikerush (Eleocharis nitida)

Neat spikerush is a colonizer of small wet localized depressions, such as shallow ditches, pits, trails, and wheel ruts in sand, gravel, or clay (MDNR, 2021b). One population of neat spikerush has been found within one mile of the project extents. This population of neat spikerush is located in a ditch next to the railroad, including about 100 stems within a small, less than one square meter patch (Barr, 2016). Suitable habitat for neat spikerush may be present within the creek restoration area. However, the species is listed as special concern and is not legally protected under state endangered species law. No further action is required.

### 2.0 References

Barr Engineering. 2016. Endangered, Threatened, and Special Concern Plant Species Survey Report. October 2016.

Minnesota Department of Natural Resources. 2021a. Rare Species Guide: *Cladium mariscoides*. Accessed November 24, 2021, at:

https://www.dnr.state.mn.us/rsq/profile.html?action=elementDetail&selectedElement=PMCYP04050

Minnesota Department of Natural Resources. 2021b. Rare Species Guide: *Eleocharis nitida*. Accessed November 24, 2021, at Eleocharis nitida:


https://www.dnr.state.mn.us/rsq/profile.html?action=elementDetail&selectedElement=PMCYP09180

### **Figures**

Figure 1 – Project Location Map

Figure 2 – Thirtynine Creek Restoration Area

# **Figures**





From: Bump, Samantha (DNR)

Nathaniel.Schroeder@clevelandcliffs.com To:

Andrea.Hayden@clevelandcliffs.com; Mielke, Sara (DNR); Bentley, Cliff (DNR) Cc:

Subject: FW: NHIS Review: Big & Little 39 Restoration Date: Wednesday, December 22, 2021 1:22:07 PM Attachments: Northshore Big Little 39 Restoration NHIS Review.pdf mage004.png

image005.png image007.png

Hi Nate,

I have reviewed the attached assessment of the potential for the above project to impact rare features. I concur with your assessment and have the additional comments:

- o As noted in your review, twig rush (Cladium mariscoides) and neat spikerush (Eleocharis nitida), both state-listed species of special concern, have been documented in the area and suitable habitat may be present within the restoration area. As such, we recommend minimizing or avoiding impacts in suitable habitat whenever feasible. Also, we recommend inspecting and cleaning all equipment prior to bringing it to the site to prevent the introduction and spread of invasive species. Please reference the resources available for native vegetation establishment and management and stream restoration.
- o Canada Lynx (Lynx canadensis), federally listed as threatened and state-listed as special concern, has been documented in the vicinity of the proposed project. This species is found in large tracks of boreal and mixed conifer-hardwood forest where they are highly dependent on snowshoe hare for prey. Population densities in the U.S. are typically lower than that of Canada. To determine conservation measures required or recommended by the U.S. Fish and Wildlife Service (USFWS), review your project in IPac. For additional information on this species, review the USFWS Canada Lynx Fact Sheet.

The reference number for this correspondence is ERDB #20220067. Thank you for notifying us of this project, and for the opportunity to provide comments.

Have a great day,

### Samantha Bump

NHIS Review Specialist | Ecological & Water Resources

### **Minnesota Department of Natural Resources**

Samantha.Bump@state.mn.us









From: Mielke, Sara (DNR) <sara.mielke@state.mn.us>

Sent: Thursday, December 2, 2021 1:55 PM

To: Bump, Samantha (DNR) <samantha.bump@state.mn.us>

Cc: Joyal, Lisa (DNR) < lisa.joyal@state.mn.us>; Fairman, Kate (DNR) < kate.fairman@state.mn.us>

Subject: FW: NHIS Review

From: Schroeder, Nathaniel A < Nathaniel. Schroeder@clevelandcliffs.com >

Sent: Thursday, December 2, 2021 7:23 AM

To: Mielke, Sara (DNR) <sara.mielke@state.mn.us>; Fairman, Kate (DNR) <kate.fairman@state.mn.us>

Cc: Hayden, Andrea J < Andrea. Hayden@clevelandcliffs.com >

Subject: NHIS Review

### This message may be from an external email source.

Do not select links or open attachments unless verified. Report all suspicious emails to Minnesota IT Services Security Operations Center.

### Good morning,

We had Barr complete the Threatened and Endangered Species review for us. I have attached this review. I looked to see who to send this to and it looks like "Regional Program staff" where the project is proposed would be the normal path forward. Since you are the reviewers, does NSM send directly to you for concurrence? I worried that if I send it directly to the Region 2 reviewer it may not be properly applied to the project.

I have attached the review, but if I should send it to someone else please let me know. I hope to have the EAW and spreadsheet responses complete today.

Please advise,



CLEVELAND-CLIFFS INC. Northshore Mining Company 10 Outer Drive Silver Bay, MN 55614 clevelandcliffs.com

This electronic message and any attachments included with this message are for the exclusive use of the individual or entity to which it is intended to be addressed. This message may contain information that is privileged or confidential and thereby exempt and protected from unauthorized disclosure under applicable law. If the reader of this message is not the intended recipient, or an employee or agent responsible for delivering the message to the intended recipient, be aware that any disclosure, dissemination, distribution or copying of this communication, or the use of its contents, is not authorized and is strictly prohibited. If you have received this communication and are not the intended recipient, please notify the sender immediately and permanently delete the original message from your e-mail system.

# Appendix C, Climate Trend Analysis and Carbon Footprint Estimation Data Sources and Output

### Summary of Estimated Mobile GHG Emissions

1	1 gram =	1.1023E-06	short ton
I	life of		
F	Project =	50	years
7	Time of		
(	construction		
-	=	3	months

											Fuel	Amount	CO <sub>2</sub> Emis	sion Factors <sup>1</sup>	CH <sub>4</sub> Emi	sion Factors	N₂O Emi	ssion Factors	· '	-		
Source Type ID	Emission Source	Number of Units <sup>10</sup>	Hours of Operation/ye ar <sup>7</sup>	Vehicle Type	Estimated Vehicle Year <sup>8</sup>	Fuel Type	MPG	VMT/day	horsepower if applicable	hp-hr if applicable	Value <sup>6</sup>	Unit	Value	Unit	Value	Unit	Value	Unit	CO <sub>2</sub> (tons/year)	CH <sub>4</sub> (tons/year)	N₂O (tons/year)	CO₂e (tons/year)
	Construction - gasoline mobile			Passenger																		
DE-3	sources On-Road	4	100	Cars	2007	Gasoline	20	14	N/A	N/A	521	total gallons	8.78	kg CO₂/gallon	0.0072	g CH <sub>4</sub> /mile <sup>3</sup>	0.0052	g N <sub>2</sub> O/mile <sup>3</sup>	1.68	0.000000	0.000000	1.68
				Medium- and																		
	Construction - diesel mobile sources -			Heavy-Duty																		1
DE-3	On-Road	2	100	Trucks	2007-2018	Diesel	15	5	N/A	N/A	548	total gallons	10.21	kg CO₂/gallon	0.0095	g CH <sub>4</sub> /mile <sup>4</sup>	0.0431	g N₂O/mile <sup>4</sup>	2.05	0.000000	0.000001	2.05
	Construction - diesel mobile sources -																					
DE-3	On-Road	2	100	Light Trucks	2007-2018	Diesel	14	5	N/A	N/A	511	total gallons	10.21	kg CO₂/gallon	0.029	g CH <sub>4</sub> /mile <sup>4</sup>	0.0214	g N₂O/mile <sup>4</sup>	1.92	0.000000	0.000000	1.92
	Construction - diesel mobile sources -			Construction																		
DE-3	Nonroad	7	500	Equipment <sup>9</sup>	N/A	Diesel	N/A	N/A	100	350000	4,375	total gallons	10.21	kg CO <sub>2</sub> /gallon	0.2	g CH <sub>4</sub> /gallon <sup>2</sup>	0.47	g N <sub>2</sub> O/gallon <sup>2</sup>	16.41	0.000019	0.000045	16.43
Notes:																		TOTAL	16.41	0.000019	0.000045	22.08

- (2) Table 5, Mobile Combustion CH<sub>4</sub> and N<sub>2</sub>O for Non-Road Vehicles. Emission Factors for Greenhouse Gas Inventories, EPA CCCL. April, 2021. https://www.epa.gov/climateleadership/ghg-emission-factors-hub
  (3) Table 3, Mobile Combustion CH<sub>4</sub> and N<sub>2</sub>O for On-Road Gasoline Vehicles. Emission Factors for Greenhouse Gas Inventories, EPA CCCL. April, 2021. https://www.epa.gov/climateleadership/ghg-emission-factors-hub
- (4) Table 4, Mobile Combustion CH<sub>4</sub> and N<sub>2</sub>O for On-Road Diesel and Alternative Fuel Vehicles. Emission Factors for Greenhouse Gas Inventories, EPA CCCL. April, 2021. https://www.epa.gov/climateleadership/ghg-emission-factors-hub
- (5) Includes equipment, such as excavators, haul trucks, skid steers
- (6) for Nonroad sources, fuel amount is calculated based on fuel usage estimates per horsepower-hour (0.05 gallons for diesel, 0.12 gallons for gasoline) from Table A9-3E in SCAQMD CEQA Air Quality Handbook (https://www.cwd.org/ArchiveCenter/ViewFile/Item/608).
- (7) Based on 10 hrs/day, 5 days/week for 16 weeks for construction
- (8) Values based off of the most conservative year (2007) for the most recent year average for medium- and heavy-duty tricks and light trucks (2007-2018). https://www.epa.gov/climateleadership/ghg-emission-factors-hub (9) Includes equipment, such as dumpers, and excavators, as well as fuel consumption from trucks that are used off-road in construction.
- (10) Numbers are based on a hypothetical assessment and not from a specific source.

### **Summary of GHG Sources and Sinks From Land Use Changes**

Source Type ID	Emission Source	Area (acres)	Net CO <sub>2</sub> Flux for land use conversion (M metric tons CO <sub>2</sub> e) <sup>1,2</sup>	2019 Total US Land Use Change from Wetland to "other" (thousands of hectares) <sup>3</sup>	2019 Total US Land Use Change from Grassland (thousands of hectares) <sup>3</sup>	CO₂e emission factor (metric tons CO₂e/acre/year)	CO₂e Emissions (tons/year)
	Land Use Change -						
	Conversion from						
	wetlands to open						
DE-4	water "other" <sup>2</sup>	0.1	1.5	121		5.02	0.55
	Land Use Change -						
	Conversion from						
	grassland to Forest						
DE-4	Land <sup>1</sup>	1.4	-10.5		992	(4.28)	(6.61)
						Total	(6.06)

### Notes:

- (1) Table 6-24: Net CO2 Flux from Forest C Pools in Land Converted to Forest Land by Land Use Change Category, Inventory of U.S. Greenhouse Gas Emissions and Sinks: 1990 2019. https://www.epa.gov/ghgemissions/inventory-us-greenhouse-gas-emissions-and-sinks-1990-2019
- (2) Table 6-66: Net CO2 Flux from C Stock Changes in Vegetated Coastal Wetlands Converted to Unvegetated Open Water Coastal Wetlands, Inventory of U.S. Greenhouse Gas Emissions and Sinks: 1990 2019. https://www.epa.gov/ghgemissions/inventory-us-greenhouse-gas-emissions-and-sinks-1990-2019
- (3) Table 6-5: Land Use and Land-Use Change for the U.S. Managed Land Base for All 50 States, Inventory of U.S. Greenhouse Gas Emissions and Sinks: 1990 2019. https://www.epa.gov/ghgemissions/inventory-us-greenhouse-gas-emissions-and-sinks-1990-2019