



SOLID BOTTOM CREEK RESTORATION PROJECT FIGURES

















| New Channe | el Wood Benches | Riffle Keys | | | | | | | | | | | |
|------------------------|-------------------------------------|----------------|----------------------|--|---------------------------------|----------------|---------------------|------|----------|------------|-------------------------|---------------------------------------|------------------|
| 188 | 224 | 36 | | | r:!!) | Volumes - | 3 | | | | | | |
| Toe Wood Benches | Material | Riffle Keys | Material | Old Channel Plugs - Fill from New | Material | Riffle Base | Material | Sill | Material | Small Fill | Material | Weir Stones (10 each riffle) | Material |
| 157 | Wood | 28 | Class II Riprap | 143 | Cut Material, New Channel | 15 | Class III Riprap | 13 | 18" Rock | 10 | 1-3" crushed rock | 7 | 40 - 2' Rocks |
| 67 | Earthen Fill, Sod, Brush Mats | 8 | 1-3" crushec rock | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |

| Cross Section | Bankful | Bankfull | Mean | Width/ | Depth | Width of | n Creek - Calcula Entrenchment | Reach/ | | | | | TM Florest | Rosgen | Movable | |
|-----------------------|------------|-------------|------------------------|----------------|-------|--------------------------|-----------------------------------|------------------|-----------|-----------------------------|-----------|------------|----------------------------|--------------------------|------------------|------------------------------|
| Station | Area (ft²) | Width (ft²) | Bankfull Depth (ft) | Depth Ratio | Max | Flood-Prone Area (ft) | Ratio | Feature Slope | LEP Lat | LEP Long | REP Lat | KEP LONG | TW Elevation | Stream Classification | Particle (mm) | Notes |
| Riffle 0+35 | 8.7 | 15.5 | 0.56 | 27.6 | 1.29 | 24 | 1.5 | 0.006 | 47.149032 | -95.531515 | 47.148764 | -95.531992 | 1512.378 | B4c | 43 | |
| Riffle 0+85 | 11.1 | 17.2 | 0.65 | 26.4 | 1.28 | 21 | 1.2 | 0.006 | 47.148868 | -95.531469 | 47.148573 | -95.532037 | 1512.184 | F4 | 51 | |
| Pool 2+15 | 17.5 | 15.6 | 1.12 | 14.0 | 1.84 | 38 | 2.5 | 0.004 | 47.148424 | -95.531467 | 47.148654 | -95.532317 | 1510.855 | | 55 | |
| Riffle 2+65 | 9.8 | 14.7 | 0.67 | 22.0 | 1.06 | 36 | 2.4 | 0.010 | 47.148321 | -95.531599 | 47.148597 | -95.532070 | 1511.202 | C4c- | 77 | |
| Split 4+24 | 19.4 | 22.9 | 0.85 | 26.9 | 1.43 | 44 | 1.9 | 0.014 | 47.148194 | -95.532038 | 47.148553 | -95.532377 | LC/1507.873 RC/1508.178 | B4c | 119 | Split channe Right is mai |
| Riffle 4+77 | 10.4 | 11.3 | 0.92 | 12.3 | 1.49 | 23 | 2.1 | 0.014 | 47.148065 | -95.532167 | 47.148529 | -95.532411 | 1507.763 | B4c | 120 | |
| xisting Riffle Mean | 10.0 | 14.7 | 0.70 | 22.1 | 1.28 | 26 | 1.8 | 0.010 | | | | | | B4c | 73 | |
| Existing Pool Mean | 17.5 | 15.6 | 1.12 | 14.0 | 1.84 | 38 | 2.5 | 0.004 | | | | | | | 55 | |
| Design Typical Riffle | 11.3 | 15.0 | 0.75 | 20.0 | 1.30 | 25 | 1.7 | 0.100 | | | | | | B4c | 464 | Design riffle |
| Design Typical Pool | 23.2 | 16.5 | 1.41 | 12.0 | 3.10 | 32 | 2.2 | 0.003 | | | | | | | 53 | Design Poo |
| | | | | | | | | | | | | | | | | |
| | Ja | nuar | y 20 | 15 | Tab | le 2. S | olid Bo | ttom | | x restor Bottom C | - | Ŭ | - | ologic | al fea | atures. |

| | | | So | lid Botto | m Creek | Patterr | n Geome | etry - Ex | isting and I | Design | | | | |
|------------------|-----------|-------------|-------------|--------------|------------|------------|------------|----------------------|--------------------------------|---|-----------------|--------------------------|----------------------------|-----------|
| | R | ladius of C | ùrvature (f | ft) | Ме | ander Be | lt Width | (ft) | Meander Belt Width Ratio | Valley Length (ft) | Valley Slope | Stream Length (ft) | Stream Overall Slope | Sinuosity |
| | N | Max | Min | Mean | Number | Max | Min | Mean | | | | | | |
| Existing Stream* | 7 | 83 | 20 | 46 | 53 | 76 | 19 | 48 | 3.2 | 532 | 0.02 | 807 | 1.36% | 1.5 |
| Design Stream | 3 | 36 | 25 | 29 | 3 | 73 | 33 | 53 | 3.5 | 532* | 0.02 | 799* | 1.38%* | 1.5 |
| *Reference data | including | surroundir | ng reach an | d restored r | reach. *Re | eference a | and design | n slope th | nrough projec | t area is 1%. | | | | |
| | | | | | | | | | | | | | | |
| MNDNR | Jan | uary | 2015 | Table 3 | 3. Solid | d Botte | So | lid Botto vironme | m Creek Res | project p toration Proj nent Workshe 7, MN | ect | geome | try. | |

| Natural Heritage | SHPO |
|--|---|
| NH findings within 1.5 miles of site, submit to Lisa Joyal – 3/21/11 | The SHPO review is waiting for NH review of documents |
| 4/24/11 - This area has been preliminarily identified by the Minnesota County Biological Survey as a sedge meadow native plant community within a Site of Moderate Biodiversity Significance. To protect this area during construction, disturbance should be minimized as feasible. This may include, but is not limited to, the following recommendations: (1) As much as possible, operate within already-disturbed areas; (2) Minimize vehicular disturbance in the area (allow only vehicles necessary for project completion); (3) Do not park equipment or stockpile supplies in the area; (4) If possible, do work in autumn or winter, to avoid damaging plants during the growing season; (5) Reduce runoff by completing the work as rapidly as possible and using erosion control measures such as straw bales or silt fencing; and (6) Re- vegetate disturbed soil with native species suitable to the local habitat as soon after construction as possible, to decrease the opportunity for | 4/24/11 – Submitted to Mike Magner for review 4/27/11 – comments from Mike Magner - It appears that this undertaking should not impact intact upland soils. No cultural resource review is recommended. |
| | 4/24/11 - This area has been preliminarily identified by the Minnesota County Biological Survey as a sedge meadow native plant community within a Site of Moderate Biodiversity Significance. To protect this area during construction, disturbance should be minimized as feasible. This may include, but is not limited to, the following recommendations: (1) As much as possible, operate within already-disturbed areas; (2) Minimize vehicular disturbance in the area (allow only vehicles necessary for project completion); (3) Do not park equipment or stockpile supplies in the area; (4) If possible, do work in autumn or winter, to avoid damaging plants during the growing season; (5) Reduce runoff by completing the work as rapidly as possible and using erosion control measures such as straw bales or silt fencing; and (6) Re- vegetate disturbed soil with native species suitable to the local habitat |