## Upper Lightning Lake Water Level Management Environmental Assessment Worksheet

## Attachment B

Preliminary Design Plans for Structure and Upstream Channel




# DUCKS UNLIMITED, INC.


## UPPER LIGHTENING LAKE PUMP

SECTION 36 TOWNSHIP 131N, RANGE 44W OTTER TAIL COUNTY, MN

IN COOPERATION WITH

MINNESOTA DEPARTMENT OF NATURAL RESOURCES





MAP POINT "A" IS LOCATED AT INTERSECTION OF STATE HWY 55 AND COUNTY HWY 11 LOCATED IN WENDELL, MN. TO SITE FROM MAP POINT, GO NORTH ON COUNTY HWY 11 ±5.0 MILES TO INTERSECTION OF COUNTY HWY 11 & COUNTY HWY 26. GO WEST ON COUNTY HWY 26 ±3 MILES TO PROJECT SITE LOCATED ON NORTH SIDE OF HIGHWAY.



### PLAN INDEX

PROJECT LOCATION MAPS
ESTIMATED QUANTITIES AND CONSTRUCTION NOTES
PROJECT TOPOGRAPHY

PROJECT TOPOGRAPHY
PLAN & PROFILE INLET CHANNEL, DETAILS AND NOTES
PLAN VIEW STRUCTURES AND STAKING LAYOUT
INTAKE SLOPED END & LIFT STATION DETAILS
DIP/SHEETING DETAILS AND NOTES
WATER CONTROL STRUCTURE DETAILS AND NOTES
HANDRAIL DETAILS
GALVANIZED STOPLOG STORAGE BOX
24"Ø RCP DETAILS AND NOTES
PLAN VIEW EROSION CONTROL
STORM WATER POLLUTION PREVENTION PLAN

### LOCATION MAP NOT TO SCALE

PROJECT AGENCY/OWNER CONTACTS: KEVIN KOTTS or TODD CALL MN DNR-GLENWOOD OFFICE 320-634-4573

PROJECT ENGINEER:
DOUG LIPETZKY, P.E.
FOR DUCKS UNLIMITED, INC.
DU - BISMARCK, ND

IF THESE PLANS ARE NOT PLOTTED AND/OR REPRODUCED AT THE ORIGINAL SIZE OF  $24"\times~36"$  ANY SCALE REFERENCED HEREIN SHOULD BE DISREGARDED AND THE PLANS SHOULD BE CONSIDERED "NOT TO SCALE."

## VICINITY MAP

This material, data and information is the property of Ducks Unlimited, Inc. It may not be used or reproduced for any purpose without the prior written consent of an authorized agent of Ducks Unlimited, Inc. Ducks Unlimited, Inc. makes no representation or warranty of any kind regarding this material, data and information, including, but not limited to, the accuracy of the material, data and information or its suitability for any purpose. All use of the material, data and information is at the users sole risk. By using any of this material, data and information, user agrees that Ducks Unlimited, Inc. is not responsible for their use of the material, data and information or the results thereof.

DESIGNED BY: DJL

DRAWN BY: MLO

SURVEYED BY: GLJ CHECKED BY: .

Revisions	Date	By		this plan, specification or repo direct supervision and that I a		DU(	CKS 📴	ROJECT NO. MN-332	2-2
이미 근미	ПП		Licensed Professional	Engineer under the laws of th		ŪŇI	LIMITED	UPPER LIGHTEN	IING LAKE PUMP
건지기기		\V/	Minnesota.	IKY YY		L INC		COVER	SHEET
<del>                                     </del>		$\overline{}$				GREAT PLAINS REGION	AL OFFICE		•
			Douglas J. Lipetzky,		ite	DATE:	SHEET NO.	APPROVED BY:	APPROVED
			for Ducks Unlimited,	Inc.					
			License No. 18843			2-5-2014	1 OF 17		

#### **ESTIMATED QUANITITES:**

OTE	SPEC.#	<u>ANITITES</u> :   Item	UNIT	QUANTITY
1	201	MOBILIZATION	LUMP SUM	1
2	202	SITE PREPARATION	LUMP SUM	1
2	202	SITE PREPARATION-DISKING	ACRE	4.0
3	203	EXCAVATION		
		MAIN CHANNEL	LINEAR FEET	2,850
		SIDE CHANNEL	LINEAR FEET	60
4	204	EMBANKMENT	CUBIC YARDS	692
5	301	WATER CONTROL STRUCTURE		
5		DOUBLE PRECAST 10'x10' SLOPED END SECTION SQ. CORNER	LUMP SUM	1
5		VERTICAL DOUBLE PRECAST 10'x8' REINFORCED CONCRETE BOX "LIFT STATION" SQ. CORNER	LUMP SUM	1
5		MODIFIED PRECAST 8'x6' REINFORCED CONCRETE UTILITY BOX	LUMP SUM	1
	302	STRUCTURE & CULVERT APPURTENANC	ES	
		ALUMINUM CANAL GATE WITH CAST IRON PEDESTAL AND GEARED LIFT	EACH	2
		ALUMINUM HATCH WITH SERIES X RETRO GRATE (54"x 42")	EACH	2
		FLAP VALVE FOR 12" DIP "COMPRESSION STYLE"	EACH	2
	303	CULVERT SUPPLY & INSTALLATION		
		24"ø RCP, GASKETED, CLASS III	LINEAR FEET	24
		12"ø DIP, PRESSURE CLASS 250	LINEAR FEET	45
	305	RIPRAP, REVETMENT & AGGREGATE PLACEMENT		
6		RIPRAP (DU CLASS II)	TON	90
7		¾"-1½" CLEAR ROCK	TON	160
8		MnDOT CLASS 5 GRAVEL	TON	120
	307	SHEET PILE MATERIAL	SQUARE FEET-PLAN	1,678
	307	SHEET PILE INSTALLATION	SQUARE FEET-PLAN	1,678
	307	PILE PRO CF 90 OR CF TEE 20 L.F. LONG MATERIAL & INSTALLATION	EACH	2
	309	STRUCTURAL STEEL		
		PILE CAP, ANGLES BOLTED TO LIFT STATION, AND FILLER PLATES	LUMP SUM	1
		CONTROL PANEL ENCLOSURE	LUMP SUM	1
		ALUMINUM STOPLOGS	LUMP SUM	1
		ALUMINUM CLEANING RAKE	LUMP SUM	1
		GALVANIZED HANDRAILS AND CHAIN ASSEMBLY MOUNTED TO SHEETING	LUMP SUM	1
		GALVANIZED STEEL GRATING	SQUARE FEET	63
		GALVANIZED STOPLOG CHANNELS, PLATES, BOLTS, HANDRAIL, LIFTING HOOKS & LOCKING ROD FOR W.C.S.	LUMP SUM	1
		GALVANIZED TRASH SCREEN AND HANDRAIL FOR INTAKE DOUBLE PRECAST SLOPED END SECTION	LUMP SUM	1
		GALVANIZED STOPLOG STORAGE BOX	EACH	1
9	313	5,000 GPM PUMP (12" HYDROMATIC MODEL S12L SUBMERSIBLE NON- CLOG PUMP OR APPROVED EQUAL (5,000 GPM AT 12-19 FT TDH)	EACH	2
	313	CONTROL PANEL WITH VARIABLE FREQUENCY DRIVE	LUMP SUM	1
	315	PUMP AND PANEL ELECTRICAL CONNECTIONS	LUMP SUM	1
0		TRAFFIC CONTROL	LUMP SUM	1
11		COFFERDAM	LUMP SUM	1
12	401	FLOATING SILT FENCE/CURTAIN	LINEAR FEET	40
12	401	STANDARD SILT FENCE	LINEAR FEET	300
12	401	MnDOT CAT. 3 EROSION BLANKET	SQUARE YARD	420
	401		·	
3	401	12"Ø STRAW WATTLES	LINEAR FEET	60
		TEMPORARY CONSTRUCTION ENTRANCE	EACH CUM	2
12	401	STORM WATER PERMIT	LUMP SUM	1
14	402	SEEDING	ACRE	4.0
14	402	MULCHING	ACRE	4.0

### ¾"-1¼" CLEAR ROCK BEDDING

LOCATION	QUANTITY
BEDDING & BACKFILL FOR SLOPED END AND LIFT STATION	120 TON
BEDDING & BACKFILL RCP	20 TON
BEDDING W.C.S. AND MISC.	20 TON
TOTAL	160 TON

#### SEEDING & MULCHING

LOCATION	QUANTITY		
STRUCTURE AREA	0.1 ACRES		
SPOIL MATERIAL FROM CH. EXCAVATION	3.9 ACRES		
TOTAL	4.0 ACRES		

#### SEED MIX

	Mixture: 35	0			
Common Name	PLS R	ate	% of Mix Component		
	kg/ha	lb/ac			
Bluestem, big	3.4	3.0	21.5		
Indian grass	2.8	2.5	18.0		
Bluestem, little	2.8	2.5	18.0		
Grama, sideoats	3.4	3.0	21.5		
Wild-rye, Canadian	2.2	2.0	14.0		
Switch grass	1.1	1.0	7.0		
Grass Totals	15.7	14.0	100.0		
	Bulk	% of Mix			
Common Name	kg/ha	lb/ac	Component		
Winter Wheat*	62.7	56.0	80.0		
Rye-grass, annual	12.5	11.2	16.0		
Wheatgrass, slender	3.1	2.8	4.0		
Cover Crop Totals	78.3	70.0	100.0		
Mesic Forbs Mixture	0.6	0.5	100.0		
GRAND TOTALS:	94.6	84.5	100.0		

\*Oats to be substituted for spring plantings

Application: Native mix for general roadside areas.

SEED MIX NOTE: MINNESOTA DNR SHALL APPROVE FINAL SEED MIX. IF MIX DIFFERS FROM THAT SHOWN, DNR WILL PROVIDE A

### UTILITIES NOTE

LOCAL NATIVE SEED MIX.

BEFORE THE START OF CONSTRUCTION, THE OWNER OF ANY UTILITIES INVOLVED MUST BE NOTIFIED. THE EXCAVATOR/CONTRACTOR IS RESPONSIBLE FOR GIVING THIS NOTICE BY CALLING "GOPHER STATE ONE CALL" AT 800–252–1166 AT LEAST 48 HOURS PRIOR TO ANY EXCAVATION. NOTE: THERE ARE OVERHEAD POWER LINES AND POWER POLE IN THE CONSTRUCTION AREA.

### CONSTRUCTION NOTES:

- BID ITEM FOR MOBILIZATION SHALL INCLUDE THE SUPPLY OF ALL LABOR, MATERIAL AND EQUIPMENT TO TRANSPORT ALL NEEDED LABOR, MATERIAL AND EQUIPMENT TO AND FROM A PROJECT SITE TO SUCCESSFULLY COMPLETE THAT PROJECT AS SHOWN ON THE PLANS OR DESCRIBED BY THE ENGINEER. CONTRACTOR SHALL ASSUME MULTIPLE MOBILIZATIONS TO RETURN WHEN WATER LEVELS HAVE LOWERED OR DURING WINTER MONTHS TO CONSTRUCT FULL INLET CHANNEL AS SHOWN.
- THE PAY QUANTITY FOR THE SITE PREPARATION BID ITEM SHALL INCLUDE STRIPPING BENEATH EMBANKMENT PAD FOOTPRINT, BORROW AREA, AND WATER CONTROL STRUCTURES. THE CONTRACTOR SHALL PLACE MIN. 6" TOPSOIL OVER ALL DISTURBED AREAS AND LEVEL SUITABLE ENOUGH FOR SEEDING & MULCHING, AS DETERMINED BY THE DU FIELD ENGINEER.

- 2) THE BID ITEM "SITE PREPARATION—DISKING" IS FOR DISKING THE SPOIL AREAS AND TRAILS WHERE POSSIBLE WITH TWO PASSES (MINIMUM) WITH A HEAVY DUTY DISK TO PREPARE THE SEEDBED. ONLY THE ACTUAL AREA DISKED WILL BE PAID FOR.
- 3) BID ITEM FOR EXCAVATION—MAIN CHANNEL & SIDE CHANNEL IS TO CONSTRUCT CHANNELS FROM STRUCTURE LOCATION OUT INTO UPPER LIGHTNING LAKE. ALL MATERIAL WILL BE REMOVED FROM WETLAND AND HAULED TO DESIGNATED WASTE/BORROW AREA AS NOTED IN THESE PLANS. PAYMENT WILL BE BASED ON LINEAR FEET. CONTRACTOR WILL ONLY BE PAID FOR THE EXACT AMOUNT OF LINEAR FEET EXCAVATED IN THE FIELD. CONTRACTOR SHALL INCLUDED ALL COSTS ASSOCIATED WITH CHANNEL EXCAVATION AND NOTED IN THESE PLANS. SEE MORE DETAILS SHEET 4.
- BID ITEM FOR EMBANKMENT SHALL BE FOR HAULING, PLACING, AND COMPACTING MATERIAL FOR THE EMBANKMENT PAD. THE QUANTITY INCLUDES THE SITE PREPARATION VOLUME PLUS 15% FOR SHRINKAGE. THIS IS A PLAN QUANTITY, THERE WILL BE NO ADJUSTMENT MADE FOR INCREASE OR DECREASE TO QUANTITY, THERE WILL BE NO ENGINEER WILL EXCAVATE TEST HOLE TO FIND SUFFICIENT MATERIAL. EMBANKMENT MATERIAL WILL BE MINED, DELIVERED TO SITE, PLACED, AND COMPACTED WITHIN STRUCTURE AREA AS DETAILED IN THESE PLANS. SPOIL MATERIAL WILL BE USED TO FILL VOID AFTER ALL MATERIAL HAS BEEN PLACED AND COMPACTED. EMBANKMENT MATERIAL WILL BE PLACED AND COMPACTED EMBANKMENT SPECIFICATION 204. EMBANKMENT MATERIAL REQUIRED BENEATH EXISTING GROUND AROUND WATER CONTROL STRUCTURE, SLOPED END, LIFT STATION, AND 24°Ø RCP SHALL BE CONSIDERED INCIDENTAL TO THOSE LINE ITEMS.
- 5) BID ITEMS UNDER SPECIFICATION 301 "WATER CONTROL STRUCTURES" SHALL INCLUDE ANY SURFACE OR SUBSURFACE WATER CONTROL NEEDED TO ALLOW INSTALLATION OF THE STRUCTURES. ANY FOREIGN MATERIAL PLACED IN A WETLAND FOR THE PURPOSE OF WATER CONTROL SHALL BE REMOVED IN ITS ENTIRETY AFTER COMPLETION OF CONSTRUCTION
  - DOUBLE PRECAST 10'x10' SLOPED END SECTION SQUARE CORNER SHALL INCLUDE 16 L.F. STRUCTURE WITH SMOOTH DOWNSTREAM SURFACE (NO MALE JOINT), DROPPED END WALL, TIE RODS, CONCEAL PRODUCTS, AND ANY OTHER ITEMS NEEDED TO COMPLETE STRUCTURE AS DETAILED THESE SHEETS. TRASH SCREEN, CLEANING RAKE, AND HANDRAIL WILL BE BID UNDER SEPARATE LINE ITEM.
  - VERTICAL DOUBLE PRECAST 10'x8' REINFORCED CONCRETE BOX CULVERT "LIFT STATION" WITH SQUARE CORNERS SHALL INCLUDE RISER SECTIONS WITH CIRCULAR KNOCKOUTS FOR 30" CANAL GATES, RECTANGULAR KNOCKOUT NEAR BOTTOM OF CENTER WALL, 14" CIRCULAR KNOCKOUTS FOR 12" Ø DIP OUTLET PIPE, 8" CONCRETE COVER (OR THICKNESS RECOMMENDED BY SUPPLIER) WITH KNOCKOUT FOR HATCH OPENINGS, 12" THICK MONOLITHIC BASE, CONCEAL PRODUCTS, TIE RODS, CONCRETE COLLAR, GROUTING IN VOIDS AROUND 12" DIPS, AND ANY OTHER ITEMS NEEDED TO COMPLETE STRUCTURE AS DETAILED THESE SHEETS. ALUMINUM HATCHES, CANAL GATES, PUMPS, CONTROL PANEL AND ELECTRICAL WORK WILL BE BID UNDER SEPARATE LINE ITEMS.
  - MODIFIED PRECAST 8'x6' UTILITY BOX SHALL INCLUDE GALVANIZED PLATES CAST ALONG SIDES OF STRUCTURE, CONCRETE COLLAR AROUND RCP, GROUTING IN VOIDS AROUND DIPS, MONOLITHIC BASE, CIRCULAR KNOCKOUTS FOR 12" DIPS, 24"Ø RCP AND ANY OTHER ITEMS NEEDED TO COMPLETE STRUCTURE AS DETAILED THESE SHEETS. GRATING, HANDRAILS, STOPLOGS, STORAGE BOX AND STOPLOG GUIDES WILL BE BID UNDER SEPARATE LINE ITEMS.
- BID ITEM FOR RIPRAP DU CLASS II IS FOR CHANNELS BOTTOM AND SIDE SLOPES NEXT TO STRUCTURES AS SHOWN SHEET 5. NON-WOVEN FILTER FABRIC IS REQUIRED BENEATH ALL ROCK RIPRAP AND SHALL BE SECURED TO SLOPES AND BOTTOM USING PINS AS NOTED SPECIFICATION 303. QUANTITIES ARE BASED ON TONS. CONTRACTOR SHALL PROVIDE SCALE TICKETS WITH WEIGHTS INCLUDING TARE WEIGHTS, GROSS WEIGHTS, AND NET WEIGHTS OF MATERIAL DELIVERED. RIPRAP SUPPLY SOURCE SHALL BE IDENTIFIED FOR INSPECTION BY THE DNR FOR INVASIVE SPECIES PRIOR TO TRANSPORTING ONSITE.
- 7) BID ITEM FOR ¾"-1½" CLEAR ROCK IS FOR BEDDING & BACKFILLING THE LIFT STATION, BEDDING THE SLOPED END SECTION, BEDDING & BACKFILLING RCP OUTLET PIPE, AND BEDDING WATER CONTROL STRUCTURE. THE DU FIELD ENGINEER WILL HAVE THE AUTHORITY TO ADD/DECREASE QUANTITY BASED ON SITE CONDITIONS AND SOIL FOUNDATION. CONTRACTOR WILL ONLY BE PAID FOR THE AMOUNT OF ROCK USED. QUANTITY IS BASED ON TONS. CONTRACTOR SHALL PROVIDE SCALE TICKETS WITH WEIGHTS INCLUDING TARE WEIGHTS, GROSS WEIGHTS AND NET WEIGHTS OF MATERIAL DELIVERED.
- BID ITEM FOR MNDOT CLASS 5 GRAVEL IS FOR SURFACING THE COUNTY HIGHWAY SLOPE AND TRANSITIONING ROAD SHOULDER TO EMBANKMENT TOP AS DETERMINED IN THE FIELD. CONTRACTOR WILL BE REQUIRED TO STRIP 6" DEPTH OF TOPSOIL PRIOR TO GRAVEL PLACEMENT. MATERIAL SHALL BE PLACED AND COMPACTED AS DETERMINED IN THE FIELD. MNDOT CLASS 5 GRAVEL SHALL BE APPROVED PRIOR TO DELIVERY ONSITE. QUANTITY IS BASED ON TONS. CONTRACTOR SHALL PROVIDE SCALE TICKETS INCLUDING TARE WEIGHTS, GROSS WEIGHTS, AND NET WEIGHTS OF MATERIAL DELIVERED.
- 9) THE BID ITEM FOR "5,000 GPM PUMP" INCLUDES THE 12" HYDROMATIC MODEL S12L NON-CLOG ELECTRICAL SUBMERSIBLE PUMP (OR APPROVED EQUAL), MOTOR, BASE ELBOW & SEALING FLANGE, TOP ELBOW, FLOATS, SWITCHES, GUIDE RAIL BRACKETS, RAILS, STAINLESS STEEL METAL INTERLOCKED POWER CORD PROTECTIVE SLEEVES ON PUMP POWER CORDS AND FLOAT SWITCHES, HANGER FOR FLOAT CORDS, STAINLESS STEEL LIFTING CHAIN ASSEMBLY, AND ANY OTHER FEATURES NECESSARY TO PROVIDE A COMPLETE OPERATIONAL PUMPING UNIT. SEE NOTES ON SHEET 8. THE COST OF CONTROL PANEL AND ELECTRICAL WORK SHALL BE INCLUDED IN SEPARATE BID ITEMS.

- 10) THE BID ITEM FOR TRAFFIC CONTROL IS FOR SUPPLYING, LOCATING, AND MAINTAINING ALL TRAFFIC CONTROL SIGNS DURING THE CONSTRUCTION. ADEQUATE SIGNING IN ACCORDANCE WITH MN MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES SHALL BE PROVIDED TO INCLUDE WARNING SIGNS SUCH AS "ROAD WORK AHEAD" AND/OR "SHOULDER WORK" WITH FLASHING LIGHTS LOCATED ½ MILE EAST AND WEST OF PROJECT SITE AS REQUIRED. CONTRACTOR SHALL MAINTAIN TWO—WAY TRAFFIC ON COUNTY ROAD UNLESS CERTAIN CONSTRUCTION ACTIVITIES WILL NOT ALLOW. AT SUCH TIME, FLAG PERSONS SHALL BE UTILIZED TO DIRECT TRAFFIC. ANY MNDOT/OTTER TAIL COUNTY SIGNING REQUIREMENTS SHALL BE ADHERED TO.
- 11) THE COST OF ANY COFFERDAM THAT MAY BE NEEDED FOR LIFT STATION AND WATER CONTROL STRUCTURE INSTALLATION SHALL BE INCLUDED IN THE BID ITEM FOR "COFFERDAM." THE BID SHALL INCLUDE BORROW REMOVAL, LOADING, HAULING, INSTALLING, REMOVAL, AND RECLAIMING. ALL MATERIAL SHALL BE REMOVED FROM WETLAND UPON COMPLETION OF PROJECT. THE CONTRACTOR CAN BORROW FROM SAME SOURCE AS EMBANKMENT MATERIAL. CONTRACTOR WILL BE REQUIRED TO RECLAIM AREA SUITABLE ENOUGH FOR SEEDING & MULCHING.
- ) SEVERAL BID ITEMS ARE INCLUDED FOR STORM WATER MANAGEMENT AND POLLUTION CONTROL. SUCH BIDS SHALL INCLUDE THE SUPPLY, INSTALLATION AND MAINTENANCE OF FLOATING SILT FENCE/CURTAIN, STANDARD SILT FENCE, 12" BIO-ROLLS (STRAW WATTLES), AND MIDDOT CATEGORY 3 EROSION CONTROL BLANKET. THE EXACT LOCATION AND QUANTITY WILL BE DETERMINED IN THE FIELD. EROSION CONTROL MEASURES SHALL BE INSTALLED CONCURRENTLY OR WITHIN 24 HOURS AFTER THE START OF WORK AND WILL BE MAINTAINED FOR THE DURATION OF THE PROJECT. SEE SHEETS 16-17, CONTRACTOR WILL BE PAID AT THE UNIT PRICE BID FOR THE ACTUAL QUANTITY INSTALLED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSTALL, INSPECT AND MAINTAIN THE BEST MANAGEMENT PRACTICE MEASURES REQUIRED TO PREVENT SILT AND POLLUTION RUNOFF. IF ADDITIONAL ITEMS NOT LISTED ON THE UNIT PRICE TABLE ARE NEEDED, THOSE SHALL BE CONSIDERED EXTRA WORK. THE CONTRACTOR WILL ALSO BE REQUIRED TO OBTAIN THE STORMWATER PERMIT FOR CONSTRUCTION ACTIVITIES PRIOR TO THE START OF THE CONSTRUCTION.

THE STANDARD SILT FENCE SHALL REMAIN IN PLACE FOLLOWING COMPLETION OF CONSTRUCTION. THE MNDNR IS RESPONSIBLE FOR REMOVING THE SILT FENCE ONCE FINAL STABILIZATION IS ACHIEVED. THE FLOATING SILT CURTAIN SHALL REMAIN IN PLACE UNTIL UPPER LIGHTNING LAKE IS TEMPORARILY DRAWN DOWN. REMOVAL WILL BE COMPLETED UNDER SEPARATE CONTRACT.

- 13) TWO "TEMPORARY CONSTRUCTION ACCESS" LOCATIONS HAVE BEEN IDENTIFIED. SEE SHEETS 1 & 11 FOR DETAILS. ANY CHANGE IN LOCATION SHALL BE APPROVED BY THE DU FIELD ENGINEER.
- 14) BID ITEM FOR "SEEDING" SHALL INCLUDE THE EQUIPMENT AND LABOR REQUIRED TO LEVEL AND PREPARE TOPSOIL FOR SEEDING AND MULCHING IN DISTURBED AREAS ON THE PROPERTY AS IDENTIFIED BY THE DU FIELD ENGINEER. THE "SITE PREPARATION—DISKING" BID ITEM SHOULD COVER THE COST OF MOST OF THIS REQUIRED PREPARATION.

THE CONTRACTOR IS RESPONSIBLE FOR SUPPLYING THE SEED MIX NOTED ON THIS SHEET, AND PLACING THE SEED IN ACCORDANCE WITH THESE PLANS AND DU SPECIFICATION 402. ANY VARIANCE REQUESTED FROM THE SEED MIX SHOWN THAT RESULTS IN A COST INCREASE WILL BE CONSIDERED EXTRA WORK AND PAID FOR AS SUCH. PAYMENT FOR "SEEDING" SHALL BE BASED ON ACTUAL ACRES SEEDED AFTER FINAL COMPLETION OF THE PROJECT AS DETERMINED BY THE DU FIELD ENGINEER.

WEED-FREE MnDOT TYPE 1 OR TYPE III MULCH SHALL BE APPLIED TO ALL AREAS SEEDED, AS DIRECTED BY THE DU FIELD ENGINEER. MULCH SHALL BE EVENLY APPLIED AT A 2.0 TON/ACRE RATE. PAYMENT WILL B BASED ON ACTUAL ACRES MULCHED AFTER FINAL COMPLETION OF PROJECT. THE AREA WILL BE DETERMINED BY DU FIELD ENGINEER.

#### A NOTE CONCERNING INVASIVE SPECIES REQUIREMENTS


THE MINNESOTA DNR OPERATION ORDER 113 REQUIRES PREVENTING OR LIMITING THE INTRODUCTION, ESTABLISHMENT AND SPREAD OF INVASIVE SPECIES DURING ACTIVITIES ON PUBLIC WATER AND DNR ADMINISTERED LANDS. THE CONTRACTOR SHALL PREVENT INVASIVE SPECIES FROM ENTERING INTO OR SPREADING WITHIN A PROJECT SITE BY CLEANING EQUIPMENT AND CLOTHING PRIOR TO ARRIVING AT THE PROJECT SITE. THE DNR SHALL INSPECT ALL EQUIPMENT AND CLOTHING AT THE STAGING AREA DETERMINED AT THE PRE-CONSTRUCTION MEFTING.


IF EQUIPMENT OR CLOTHING ARRIVES AT THE PROJECT SITE WITH SOIL, AGGREGATE MATERIAL, MULCH, VEGETATION (INCLUDING SEEDS) OR ANIMALS, IT SHALL BE CLEANED BY CONTRACTOR FURNISHED TOOL OR EQUIPMENT (BRUSH/BROOM, COMPRESSED AIR, OR PRESSURE WASHER) AT THE STAGING AREA. THE CONTRACTOR SHALL DISPOSE OF MATERIAL CLEANED FROM EQUIPMENT AND CLOTHING AT A LOCATION DETERMINED BY THE OWNER. IF MATERIAL CANNOT BE DISPOSED OF ONSITE, SECURE MATERIAL PRIOR TO TRANSPORT (SEALED CONTAINER, COVERED TRUCK, OR WRAP WITH TARP) AND LEGALLY DISPOSE OF OFFSITE.


IF WORK IS PERFORMED WITHIN A WATER BODY, THE CONTRACTOR SHALL CLEAN EQUIPMENT AND CLOTHING AS NOTED ABOVE, PRIOR TO ENTERING AND LEAVING THE WATER BODY. DRAIN ALL WATER FROM EQUIPMENT WHERE WATER MIGHT BE TRAPPED, SUCH AS TANKS, PUMPS, HOSES, SILT CURTAINS, AND WATER RETAINING COMPONENTS OF BOATS/BARGES.


THE SOURCES OF ALL IMPORTED MATERIAL SHALL BE INSPECTED FOR INVASIVE SPECIES BY THE DNR PRIOR TO TRANSPORTING


1	Revision Number	Sheet Number	Revisions	Date	By	I hereby certify that this plan, specification or by me or under my direct supervision and that				JECT NO. MN-332-2	ļ	DESIGNED BY:	DJL
				ПП		Licensed Professional Engineer under the laws		UNLI	IMITED 1	JPPER LIGHTENING LAKE I	PUMP I	DRAWN BY:	MLO
					1////			INC.		ESTIMATED QUANTITIES A		SURVEYED BY:	GLJ
			<del>────────────────────────────────────</del>	╘═┼	₩			GREAT PLAINS REGIONAL		CONSTRUCTION NOTES	- 10	CHECKED BY:	
						Douglas J. Lipetzky, P.E.	Date	DATE: S	HEET NO.	APPROVED BY:	APPROVED B	Y:	
						for Ducks Unlimited, Inc. License No. 18843		2-5-2014 2	OF 17				•






































STORM WATER POLLUTION PREVENTION PLAN
THE Minnesota General Permit Authorization to Discharge
Stormwater Associated with Construction Activity issued on

MNDNR: Minnesota Department of Natural Resources FWS: United States Fish & Wildlife Service MPCA: Minnesota Pollution Control Agency

Project Limits: See Sheets 3-4 of these plans for the project limits. These sheets show the embankment and lift station location, the inlet channel excavation, spoil areas

#### SITE DESCRIPTION

Project Description: The purpose of the project is to provide a means to allow the lowering of Upper Lightning Lake to original runout levels, which may promote better water quality and clear water and plant growth in the shallow lake. The lift station/pump is being located adjacent to the County road to reduce impacts that would be required if it was located closer to the lake. However, an inlet channel is needed to bring water from the lake to the lift station. Gravity discharge through the water control structure and existing road culvert will be used to the extent possible. The road culvert invert is at elevation 1083.3 and the lake bottom at  $\pm 1078-1079$ . Therefore the pumps will be used to remove water below the road culvert elevation. Minor fill is required for the embankment. The spoil from the channel will all be removed from any wetland areas, and hauled and blended into an existing

Site Map(s): See map on cover sheet of plans.

Major Soil Disturbing Activities (check all that apply):

- Clearing & Grubbing
  X Grading & Shaping
  X Cutting & Filling

Other (describe):

Total Project Area: 4.5 Acres Total Area to Be Disturbed: 4.5 Acres Existing Impervious Area: 0.0 Acres Proposed Impervious Area: 0.0 Acres

Name of Receiving Water Body/Bodies: Prior to this plan being implemented, the channel immediately downstream will be cleaned/maintained. The channel is an intermittent stream that flows through Swift WMA and Kube WMA (also known as Denton Slough). Denton Slough is at the downstream end of the channel maintenance project. This intermittent stream continues south approximately 1.5 stream miles downstream from Denton Slough, then turns west and runs about four miles before joining the Rabbit west and runs about four inlines being joining and roson.

River. The Rabbit River eventually flows into the Bois de
Sioux River and onto the Red River. See maps on Sheets

& 16 for wetlands within one mile downstream of the site. The existing channel downstream of Denton Slough is a well defined drainage channel.

Discharges to Special Or Impaired Waters: The project does not have a discharge point within 1 mile of a special water or a water that is impaired for sediment or a sediment related parameter of the permit.

Discharges to Calcareous Fen: The project does not have

Endangered or Threatened Species: The project area has

Historic Places or Archeological Sites: Historical places or

Quantities Tabulation for All BMPs: See estimated quantities

ROLL JOINTS

SILT FENCE DETAIL NOT TO SCALE

#### PROJECT CONTACTS AND RESPONSIBILITIES

The Contractor is responsible for cosigning and being familiar with the MPCA General Permit for storm water discharges associated with a construction site. When a conflict arises between the permit and this plan sheet, the

The Contractor is responsible for implementation of the SWPPP and installation, inspection and maintenance of the erosion prevention and sediment control BMP's before and

The Contractor is required to have a person designated and on the project site who has been trained and certified as either an Erosion/ Sediment Control Inspector/Installer or in Erosion/Sediment Control Site Management.

The Minnesota Department of Natural Resources (MNDNR), Glenwood Office, is responsible for long term operation and maintenance of the permanent storm water management system. The MNDNR is responsible for removal of the standard and floating silt fence ofter final stabilization is accomplished. Also, the MNDNR is responsible for filing a Notice of Termination with MPCA upon final stabilization.

The Contractor and MNDNR contact information is provided in the contract documents and on Sheet 1 of the project

Douglas J. Lipetzky, P.E., Regional Engineering Supervisor for Ducks Unlimited, Inc. prepared the SWPPP. He successfully completed the "Design of Storm Water Pollution Prevention Plans" training course sponsored by the University of Minnesota (Nov. 16–17, 2009, Mankato, MN) and recertification course (Feb. 4, 2013, St. Cloud, MN). His certification expires May 31, 2016.

#### SPILL NOTIFICATION

In the event of a spill, the contractor's site superintendent will make the appropriate notificiaton(s), consistent with the following procedures:

- 1. A reportable spill is a quantity of more than 5 gallons of petroleum which must be reported immediately to the MPCA.
- 2. Any spill of oil or hazardous substance to waters of the state must be reported immediately by telephone to the MPCA.

  3. MPCA Contact for Environmental Emergencies: 24 Hour
- (651) 649-5451 or (800) 422-0798

CONSTRUCTION CHANGES
When changes are made to the construction project that will require alterations in the temporary erosion controls of the site, the Storm Water Pollution Prevention Plan (SWPPP) will be amended to provide appropriate protection to for review over the course of the project.

NRCS Soil Survey for Otter Tail County, Minnesota

6" x 6" ANCHO

#### ORDER OF CONSTRUCTION ACTIVITIES

(Stabilization measures shall be initiated as soon as possible, but in no case later than 14 days after the construction activity in that portion of the site has temporarily or permanently ceased. However, at locations adjacent to surface water, such stabilization shall occur within 24 hours after construction activity has ceased.)

- Install erosion and sediment control measures
- Proceed with embankment and lift station construction.

  Stabilize embankment area with temporary erosion and sediment
- control measures.

  Complete inlet channel excavation and spoil placement.

  Stabilize trails and other areas disturbed by construction
- activities with temporary erosion and sediment control measures
- Complete final grading.

  Complete permanent erosion and sediment control measures.

LOCATION OF SWPPP REQUIREMENTS IN PROJECT PLAN
See Sheets 2, 4 and 15 for erosion control measures and

#### EROSION AND SEDIMENT CONTROLS (Check all that apply)

Stabilization Practices (See Erosion and Sediment Control Details in Plan Sheets)

- X Temporary or Permanent Seeding
- \_\_\_ Sod Placement
- Mulching (Straw or Cellulose Fiber) Erosion Control Blankets or Mats Vegetation Buffer Strips <u>X</u>
- X Roughened Surface (e.g. tracking)
- X Other: Riprap

Structural Temporary Erosion and Sediment Controls

X Silt Fence

- Temporary Berm Temporary Slope Drain
- X Straw Wattles or Rolls
- Diversion Channels/Swales
- Channel Liners (TRM) X Stone Rip Rap
- Sediment Trans/Basins
- \_\_\_ Outlet Protection
- Surface Inlet Protection
- Curb Inlet Protection
  X Stabilized Construction Entrances

#### Wetland Avoidance:

Will construction and/or erosion and sediment controls impinge on regulated wetlands? X Yes No
If yes, the project and erosion and sediment control impacts have been included in the total project wetland impacts and been included in the 404 permit process with the USACE.

Storm Water Management: Storm water management will be handled by temporary controls outlined in "EROSION AND SEDIMENT CONTROLS" above, and any permanent controls needed to meet permanent storm water management needs in the post

PLACE CRUSHED ROCK OVER

Date

- Pollution Prevention Management Measures

   <u>Solid Wastes</u> Collected sediment, asphalt, and concrete millings, floating debris, paper, plastic, fabric, construction and demolition debris and other wastes must be disposed of properly and must comply with the MPCA disposal requirements.
- Hazardous Materials Oil, gasoline, paint and any hazardous substances must be properly stored, including secondary containment, to prevent spills, leaks or other discharge. Restricted access to storage areas must be provided to prevent vandalism. Storage and disposal of hazardous waste must be in compliance with MPCA regulations
- <u>Vehicle Washing</u> External washing of trucks and other construction vehicles must be limited to a defined area of the site. Runoff must be contained and waste properly disposed of. No engine degreasing is allowed on site.
- Concrete Washout Onsite All liquid and solid wastes generated by concrete washout operation must be contained in a leak-proof containment facility or impermeable liner. A compacted clay liner that does not allow washout liquids to enter ground water is considered an impermeable liner. The liquid and solid wastes must not contact the ground, and there must not be runoff from the concrete washout operation or areas. Liquid and solid wastes must be disposed of properly and in compliance with MPCA regulations. A sign must be installed adjacent to each washout facility to inform concrete equipment operators to utilize the proper facilities.

#### MAINTENANCE AND INSPECTION

nintenance and Inspection Practices
Inspections will be conducted at least one time per

- eek and after a storm event of 0.50 inches o
- greater. All controls will be maintained in good working order. Necessary repairs will be initiated within 24 hours of the site inspection report or as soon as field conditions allow access.
- Where work has been suspended due to frozen ground conditions, the required inspections and maintenance must take place as soon as runoff occurs at the site
- Where parts of the construction site have undergone final stabilization, but work remains on other parts of the site, inspections of the stabilized areas may be reduced to once per month.
- Silt fence will be inspected for depth of sediment and for tears in order to ensure the fabric is securely anchored. Sediment buildup will be removed from the silt fence when it reaches % of the height of the silt fence. All silt fences must be repaired, replaced, or supplemented when they become nonfunctional or the
- sediment reaches 3 of the height of the fence.
  Sediment basins and traps will be checked. Sediment will be removed when the depth reaches approximately

NOTES

- Any check dams will be inspected for stability. Sediment will be removed when the depth reaches 75% the height of the dam. All seeded areas will be checked for bare spots,
- washouts, and vigorous growth free of significant weed
- Surface waters, including drainage ditches and conveyance systems, must be inspected for evic of sediment being deposited by erosion. Construction site vehicle exit locations must be
- inspected for evidence of off-site sediment tracking onto paved surfaces. Tracked sediment must be removed from all off-site paved surfaces within 24
- hours of discovery.
  Disturbed areas will be checked for stabilization.
  Stabilization measures shall be initiated as soon as
  construction activity in that portion of the site has temporarily or permanently ceased. The normal wetted perimeter of any temporary or
- permanent drainage ditch or swale that drains water from any portion of the construction site, or diverts water around the site, must be stabilized within 200 lineal feet from the property edge, or from the point of discharge into any surface water. Stabilization of the last 200 lineal feet must be completed within 24 hours after connection to a surface water
- Stabilization of the remaining portions of any temporary or permanent ditches or swales must be completed within 14 days after connecting to a surface water and construction in that portion of the
- ditch has temporarily or permanently ceased. Temporary or permanent ditches or swales that are being used as a sediment containment system (with properly designed rock ditch checks, bio rolls, silt dikes, etc.) do not need to be stabilized. These areas must be stabilized within 24 hours after no longer
- being used as a sediment containment system. Pipe outlets must be provided with temporary permanent energy dissipation within 24 hours after connection to a surface water.
- Discharge procedures for water control and dewatering operations will be inspected. If the water cannot be discharged to a sedimentation basin prior to entering the surface water, it must be treated with the appropriate BMPs, such that the discharge does not adversely affect the receiving water or downstream
- Inspection and maintenance reports will be completed for each site inspection, this form will also be used to for each site inspection, this form will also be used to document changes to the SWPPP. The report shall include the date and amount of rainfall events greater than 0.5 inch in 24 hours. A copy of the completed inspection form will be filed with the SWPPP
- The Contractor's site superintendent is responsible for inspection. Maintenance and repair activities are the responsibility of the Contractor.

LIPPER LIGHTNING LAKE

PREVENTION PLAN

STORM WATER POLLUTION

INC.

17 OF 17

GREAT PLAINS REGIONAL OFFICE DATE: SHEET N

2-5-2014

CONCRETE WASHOUT

LACK LETTERS,

DESIGNED BY: DJL

DRAWN BY: DJL

SURVEYED BY: GLJ

CHECKED BY: .

