



State of Minnesota Department of Transportation

Aggregates Test Report

Office of Materials and Road Research

1400 Gervais Avenue

Maplewood, MN 55109

Sample ID Number: CO-PS11-0006

Project Number: For Info Only

Field ID: DH 120
Date Sampled: 11/15/2010
Date Received: 12/09/2010
Approved: 2/24/2011 15:05
TH Number:
Depth: 1.00 to 15.00
Grade Spec:
Spec Class:
Quality Spec:
Plant Name:
Comment:

Billing Agency:
Project Engineer: D. MARTIN
Submitter: DNR- H. ARENDS
IAS Name:
Legal: SE1/4 NE1/4 Sec 33 - 123 - 35
Pit Name:
Pit Owner:
Sampled From: DRILL HOLE
Usage: DNR PROSPECTING

Test Procedures: AASHTO T-19, T-21, T-27(M), T-30(M), T-84(M), T-85(M), T-96(M), T-104(M), T-113(M), T-176(M), T-248(M), T-304 Method A, ASTM C123, ASTM C535, ASTM D3042, ASTM D4791(M), Micro Deval(MP), Percent Crushing(MP) M = MN/DOT Modified MP = MN/DOT Procedures

% Passing Sieve:	Lab Test	Field Test	Spec. Limits	
			Low	High
63mm (2 1/2")	100			
50mm (2")	100			
37.5mm (1 1/2")	97			
31.5mm (1 1/4")	96			
25.0mm (1")	95			
19.0mm (3/4")	93			
12.5mm (1/2")	89			
9.5mm (3/8")	85			
4.75mm (#4)	72			
2.36mm (#8)	54			
2.00mm (#10)	49			
1.18mm (#16)	38			
600um (#30)	21			
425um (#40)	13			
300um (#50)	8			
150um (#100)	3			
75um (#200)	2.3			
<hr/>				
% Shale in Sand	0.7			
%Total Shale +4	0.1			
%TotalSamplShale	0.6			
% Carbonate	48.5			
% Iron Oxide	0.10			
% Unsound Chert	0.03			
%TotalSamplSpall	0.6			
% BA Spall +4	0.2			

* Value does not meet Spec
~ Value out of Field Lab Tolerance
*** Trace (0.00 - 0.05) Detected
% Shale in Sand N.C. = Trace

☐ Meets Requirements
☐ Does Not Meet Requirements
☒ For Info Only
☐ Incentive/Disincentive

☐ Unable to Verify
☐ Unable to Verify, Not Enough Material Supplied
☐ Within Lab-Field Tolerance
☐ Out of Lab-Field Tolerance

Comments:
PROSPECT SAMPLE

Copies To
DNR - H. ARENDS

Charge: 1 - 1012
1 - 1013
1 - 1014
1 - 1029

Report Approved By:

David B. Bahr